Item No		Quantity	Rate	Amount
	SECTION No. 1 - PRELIMINARIES			
	BILL NO. 1			
	PRELIMINARIES			
	MEANING OF TERMS "TENDER / TENDERER"			
	Any reference to the words "Tender" or "Tenderer" herein and/or in any other documentation shall be construed to have the same meaning as the words "Bid" or "Bidder"			
	PRELIMINARIES			
	The JBCC Preliminaries Code 2103, May 2005 edition for use with the JBCC Principal Building Agreement Edition 4.1 Code 2101, March 2005 is taken to be incorporated herein. The tenderer is deemed to have referred to these documents for the full intent and meaning of each clause. These clauses are referred to by number and heading only. Where standard clauses or options are not applicable to the contract such modifications or corrections as are necessary are given under each relevant clause. Where an item is not relevant to this specific contract such item is marked "N/A" signifying "Not Applicable"			
	PRICING OF PRELIMINARIES			
	Should Option A, as set out in clause B10.3.1 hereinafter be used for the adjustment of preliminaries then each item priced is to be allocated to one or more of the three categories Fixed, Value Related or Time Related and the respective amounts entered in the spaces provided under each item			
	Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities			
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

	SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT		
	<u>DEFINITIONS</u>		
1	A1.0 DEFINITIONS AND INTERPRETATION		
	Clause 1.0		
	Clause 1.1 Definition of "Commencement Date" is added:		
	"COMMENCEMENT DATE" means the date that the agreement, made in terms of the Form of Offer and Acceptance, comes into effect		
	Clause 1.1 Definition of "Construction Guarantee" is amended by replacing it with the following:		
	"CONSTRUCTION GUARANTEE" means a guarantee at call obtained by the contractor from an institution approved by the employer in terms of the employer's construction guarantee form as selected in the schedule		
	Clause 1.1 Definition of "Construction Period" is amended by replacing it with the following:		
	"CONSTRUCTION PERIOD" means the period commencing on the commencement date and ending on the date of practical completion		
	Clause 1.1 Definition of "Corrupt Practice" is added:		
	"CORRUPT PRACTICE" means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution		
	Clause 1.1 Definition of "Fraudulent Practice" is added:		
	"FRAUDULENT PRACTICE" means a mispresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of any tenderer and includes collusive practice among tenderers (prior to or after the tender submission) designed to establish tender prices at artificial non-competitive levels and to deprive the tenderer of the benefits of free and open competition		
	Carried to Collection	R	
		"	<u></u>
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		
			ı

Clause 1.1 Definition of "Interest" is amended by replacing it with the following:			
"INTEREST" means the interest rates applicable on this contract, whether specifically indicated in the relevant clauses or not, will be the rate as determined by the Minister of Finance, from time to time, in terms of section 80(1)(b) of the Public Finance Management Act, 1999 (Act No. 1 of 1999)			
Clause 1.1 Definition of " Principal Agent " is amended by replacing it with the following:			
"PRINCIPAL AGENT" means the person or entity appointed by the employer and named in the schedule. In the event of a principal agent not being appointed, then all the duties and obligations of a principal agent as detailed in the agreement shall be fulfilled by a representative of the employer as named in the schedule			
Clause 1.1 Definition of " Security " is amended by replacing it with the following:			
"SECURITY" means the form of security provided by the employer or contractor, as stated in the schedule, from which the contractor or employer may recover expense or loss			
Clause 1.6 is amended by replacing the words "prepaid registered post, telefax or e-mail" with "prepaid registered post or telefax"			
Clause 1.6.4 is amended by replacing it with the following:			
No clause			
Fixed: Value related: Time related:	Item		
OBJECTIVE AND PREPARATION			
A2.0 OFFER, ACCEPTANCE AND PERFORMANCE			
Clause 2.0			
Fixed: Value related: Time related:	Item		
Carried to Collection		R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1

1	A3.0 DOCUMENTS			
	Clause 3.0			
	Clause 3.2.1 is amended by replacing "14.1" with "14.0"			
	Clause 3.7 is amended by the addition of the following:			
	The contractor shall supply and keep a copy of the JBCC Series 2000 Principal Building Agreement and Preliminaries applicable to this contract on the site , to which the employer , principal agent and agents shall have access at all times Clause 3.10 is amended by replacing the second			
	reference to "principal agent" with the word "employer"			
	Fixed: Value related: Time related:	Item		
2	A4.0 DESIGN RESPONSIBILITY			
	Clause 4.0			
	Clause 4.3 is amended by replacing it with the following:			
	No clause			
	Fixed: Value related: Time related:	Item		
3	A5.0 EMPLOYER'S AGENTS			
	Clause 5.0			
	Clause 5.1.2 is amended to include clauses 32.6.3, 34.3, 34.4 and 38.5.8			
	Fixed: Value related: Time related:	Item		
4	A6.0 SITE REPRESENTATIVE			
	Clause 6.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			_
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1	A7.0 COMPLIANCE WITH REGULATIONS		
	Clause 7.0		
	Note: A separate clause has been included in Section C : Specific Preliminaries of the bills of quantities / lump sum document for the contractor to have the opportunity to price for all the requirements of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification		
	Fixed: Value related: Time related:	Item	
2	A8.0 WORKS RISK		
	Clause 8.0		
	Fixed: Value related: Time related:	Item	
3	A9.0 INDEMNITIES		
	Clause 9.0		
	Fixed: Value related: Time related:	Item	
4	A10.0 WORKS INSURANCES		
	Clause 10.0		
	Clause 10.0 is amended by the addition of the following clauses:		
	10.5 Damage to the Works		
	(a) Without in any way limiting the contractor's obligations in terms of the contract, the contractor shall bear the full risk of damage to and/or destruction of the works by whatever cause during construction of the works and hereby indemnifies and holds harmless the employer against any such damage. The contractor shall take such precautions and security measures and other steps for the protection and security of the works as the contractor may deem necessary		
	Carried to Collection	R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,		
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		

(b)	The contractor shall at all times proceed immediately to remove or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works		
(c)	The employer shall carry the risk of damage to or destruction of the works and materials paid for by the employer that is the result of the excepted risks as set out in 10.6		
(d)	Where the employer bears the risk in terms of this contract, the contractor shall, if requested to do so, reinstate any damage or destroyed portions of the works and the costs of such reinstatement shall be measured and valued in terms of 32.0 hereof		
10.6 Inj Proper	ury to Persons or loss of or damage to ties		
(a)	The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever arising out of or in the course of or caused by the execution of the works unless due to any act or negligence of any person for whose actions the employer is legally liable		
(b)	The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site , whether belonging to or under the control of the employer or any other body or person, arising out of or in the course of or by reason of the execution of the works unless due to any act or negligence of any person for whose actions the employer is legally liable		
	Carried to Collection	R	
PRELIN Bill No.	MINARIES AND GENERAL (NOT TO BE PRICED,		
PRELIN	/ MINARIES AND GENERAL (NOT TO BE PRICED, .O JPS AND SONTSELE JSS		

(c)	The contractor shall, upon receiving a contract instruction from the principal agent, cause the same to be made good in a perfect and workmanlike manner at his own cost and in default thereof the employer shall be entitled to cause it to be made good and to recover the cost thereof from the contractor or to deduct the same from amounts due to the contractor			
(d)	The contractor shall be responsible for the protection and safety of such portions of the premises placed under his control by the employer for the purpose of executing the works until the issue of the certificate of practical completion			
(e)	Where the execution of the works involves the risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the contractor shall obtain adequate insurance and will remain adequately insured or insured to the specific limit stated in the contract against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion of the works has been completed			
(f)	The contractor shall at all times proceed immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the works			
10.7 H	igh risk insurance			
geolog an area condition moven	event of the project being executed in a ical area classified as a "High Risk Area", that is a which is subject to highly unstable subsurface ons that might result in catastrophic ground nent evident by sinkhole or doline formation the ng will apply:			
	Carried to Collection		R	
PRELII Bill No.	MINARIES AND GENERAL (NOT TO BE PRICED, . 1			
PRELII	MINARIES AND GENERAL (NOT TO BE PRICED, LO JPS AND SONTSELE JSS			
		İ		1

10.7.1 Damage to the works			
The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage to and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary			
When so instructed to do so by the principal agent , the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works , at the contractor's own costs			
10.7.2 Injury to persons or loss of or damage to property			
The contractor shall be liable for and hereby indemnifies and holds harmless the employer against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of, or caused by a catastrophic ground movement as mentioned above			
The contractor shall be liable for and hereby indemnifies the employer against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site , whether belonging to or under the control of the employer or any other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract			
10.7.3 It is the responsibility of the contractor to ensure that he has adequate insurance to cover his risk and liability as mentioned in 10.7.1 and 10.7.2. Without limiting the contractor's obligations in terms of the contract, the contractor shall, within twenty-one (21) calendar days of the commencement date but before commencement of the works, submit to the employer proof of such insurance policy, if requested to do so			
Carried to Collection	R		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			
			ı

	10.7.4 The employer shall be entitled to recover any and all losses and/or damages of whatever nature suffered or incurred consequent upon the contractor's default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the contractor or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the			
	employer and the contractor and for this purpose all these contracts shall be considered one indivisible whole			
	Fixed: Value related: Time related:	Item		
1	A11.0 LIABILITY INSURANCES			
	Clause 11.0			
	Fixed: Value related: Time related:	Item		
2	A12.0 EFFECTING INSURANCES			
	Clause 12.0			
	Fixed: Value related: Time related:	Item		
3	A13.0 No clause	N/A		
4	A14.0 SECURITY			
	Clause 14.0			
	Clauses 14.1 - 14.8 are amended by replacing them with the following:			
	14.1 In respect of contracts with a contract sum up to R1 million, the security to be provided by the contractor to the employer will be a payment reduction of five per cent (5%) of the value certified in the payment certificate (excluding VAT)			
	14.1.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(A)			
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			_
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

14.1.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction security or portions thereof to the contractor		
14.2 In respect of contracts with a contract sum above R1 million, the contractor shall have the right to select the security to be provided in terms of 14.3, 14.4, 14.5, 14.6, or 14.7 as stated in the schedule . Such security shall be provided to the employer within twenty-one (21) calendar days from commencement date . Should the contractor fail to select the security to be provided or should the contractor fail to provide the employer with the selected security within twenty-one (21) calendar days from commencement date , the security in terms of 14.7 shall be deemed to have been selected		
14.3 Where security as a cash deposit of ten per cent (10%) of the contract sum (excluding VAT) has been selected:		
14.3.1 The contractor shall furnish the employer with a cash deposit equal in value to ten per cent (10%) of the contract sum (excluding VAT) within twenty-one (21) calendar days from commencement date		
14.3.2 Within twenty-one (21) calendar days of the date of practical completion of the works the employer shall reduce the cash deposit to an amount equal to three per cent (3%) of the contract value (excluding VAT), and refund the balance to the contractor		
14.3.3 Within twenty-one (21) calendar days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor		
14.3.4 On the date of payment of the amount in the final payment certificate, the employer shall refund the remainder of the cash deposit to the contractor		
Carried to Collection	R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		

14.3.5 The employer shall be entitled to recover expense and loss from the cash deposit in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the cash deposit security or portions thereof to the contractor		
14.3.6 The parties expressly agree that neither the employer nor the contractor shall be entitled to cede the rights to the deposit to any third party		
14.4 Where security as a variable construction guarantee of ten percent (10%) of the contract sum (excluding VAT) has been selected:		
14.4.1 The contractor shall furnish the employer with an acceptable variable construction guarantee equal in value to ten per cent (10%) of the contract sum (excluding VAT) within twenty-one (21) calendar days from commencement date		
14.4.2 The variable construction guarantee shall reduce and expire in terms of the Variable Construction Guarantee form included in the invitation to tender		
14.4.3 The employer shall return the variable construction guarantee to the contractor within fourteen (14) calendar days of it expiring		
14.4.4 Where the employer has a right of recovery against the contractor in terms of 33.0, the employer shall issue a written demand in terms of the variable construction guarantee		
14.5 Where security as a fixed construction guarantee of five per cent (5%) of the contract sum (excluding VAT) and a five per cent (5%) payment reduction of the value certified in the payment certificate (excluding VAT) has been selected:		
14.5.1 The contractor shall furnish a fixed construction guarantee to the employer equal in value to five per cent (5%) of the contract sum (excluding VAT)		
14.5.2 The fixed construction guarantee shall come into force on the date of issue and shall expire on the date of the last certificate of practical completion		
Carried to Collection	R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		

14.5.3 The employer shall return the fixed construction guarantee to the contractor within fourteen (14) calendar days of it expiring		
14.5.4 The payment reduction of the value certified in a payment certificate shall be in terms of 31.8 (A) and 34.8		
14.5.5 Where the employer has a right of recovery against the contractor in terms of 33.0, the employer shall be entitled to issue a written demand in terms of the fixed construction guarantee or may recover from the payment reduction or may do both		
14.6 Where security as a cash deposit of five per cent (5%) of the contract sum (excluding VAT) and a payment reduction of five per cent (5%) of the value certified in the payment certificate (excluding VAT) has been selected:		
14.6.1 The contractor shall furnish the employer with a cash deposit equal in value to five per cent (5%) of the contract sum (excluding VAT) within twenty-one (21) calendar days from commencement date		
14.6.2 Within twenty-one (21) calendar days of the date of practical completion of the works the employer shall refund the cash deposit in total to the contractor		
14.6.3 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(A)		
14.6.4 Where the employer has a right of recovery against the contractor in terms of 33.0, the employer may issue a written notice in terms of 33.4 or may recover from the payment reduction or may do both		
14.7 Where security as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT) has been selected:		
14.7.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(B)		
Carried to Collection	R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED,		=
Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		

14.7.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction or portions thereof to the contractor			
14.8 Payments made by the guarantor to the employer in terms of the fixed or variable construction guarantee shall not prejudice the rights of the employer or contractor in terms of this agreement			
14.9 Should the contractor fail to furnish the security in terms of 14.2, the employer , in his sole discretion and without notification to the contractor , is entitled to change the contractor's selected form of security to that of a ten per cent (10%) payment reduction of the value certified in the payment certificate (excluding VAT), whereafter 14.7 shall be applicable			
Fixed: Value related: Time related:	Item		
EXECUTION			
A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS			
Clause 15.0			
Clause 15.1.1 is amended by replacing it with:			
No clause			
Clause 15.1.2 is amended by replacing it with:			
The security selected in terms of 14.0			
Clause 15.1 is amended by the addition of the following clause:			
15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date			
Clause 15.2.1 is amended by replacing it with the following clause:			
Carried to Collection		R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
GECELO JPS AND SONTSELE JSS			

1

	Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4			
	Fixed: Value related: Time related:	Item		
1	A16.0 ACCESS TO THE WORKS			
	Clause 16.0			
	Fixed: Value related: Time related:	Item		
2	A17.0 CONTRACT INSTRUCTIONS			
	Clause 17.0			
	Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors "			
	Fixed: Value related: Time related:	Item		
3	A18.0 SETTING OUT OF THE WORKS			
	Clause 18.0			
	Fixed: Value related:	Item		
4	A19.0 ASSIGNMENT			
	Clause 19.0			
	Fixed: Value related: Time related:	Item		
				_
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1			
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1	A20.0 NOMINATED SUBCONTRACTORS			
	Clause 20.0			
	Clause 20.1.3 is amended by replacing it with the following:			
	No clause			
	Note: See item B9.1 hereinafter for adjustment of attendance on nominated subcontractors executing work allowed for under provisional sums			
	Fixed: Value related: Time related:	Item		
2	A21.0 SELECTED SUBCONTRACTORS			
	Clause 21.0			
	Clause 21 is amended by replacing it with:			
	No clause			
	Fixed: Value related: Time related:	Item		
3	A22.0 EMPLOYER'S DIRECT CONTRACTORS			
	Clause 22.0			
	Fixed: Value related: Time related:	Item		
4	A23.0 CONTRACTOR'S DOMESTIC SUBCONTRACTORS			
	Clause 23.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1			
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

	COMPLETION			
1	A24.0 PRACTICAL COMPLETION			
	Clause 24.0			
	Fixed: Value related: Time related:	Item		
2	A25.0 WORKS COMPLETION			
	Clause 25.0			
	Fixed: Value related: Time related:	Item		
3	A26.0 FINAL COMPLETION			
	Clause 26.0			
	Clause 26.1.2 is amended by inserting "#" next to 26.1.2			
	Fixed: Value related: Time related:	Item		
4	A27.0 LATENT DEFECTS LIABILITY PERIOD			
	Clause 27.0			
	Fixed: Value related: Time related:	Item		
5	A28.0 SECTIONAL COMPLETION			
	Clause 28.0			
	Fixed: Value related: Time related:	Item		
				_
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1			
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1	A29.0 REVISION OF DATE FOR PRACTICAL COMPLETION			
	Clause 29.0			
	Clause 29.2.5 is amended by replacing it with:			
	No clause			
	Fixed: Value related: Time related:	Item		
2	A30.0 PENALTY FOR NON-COMPLETION			
	Clause 30.0			
	Fixed: Value related: Time related:	Item		
	PAYMENT			
3	A31.0 INTERIM PAYMENT TO THE CONTRACTOR			
	Clause 31.0			
	Clause 31.5.2 is amended by replacing "14.7.1" with "14.0"			
	Clause 31.8 is amended by replacing it with the following two alternative clauses:			
	Alternative A			
	31.8(A) Where a security is selected in terms of 14.1; 14.5 or 14.6, the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:			
	31.8(A).1 Ninety-five per cent (95%) of such value in interim payment certificates issued up to the date of practical completion			
	31.8(A).2 Ninety-seven per cent (97%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion			
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			_
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

31.8(A).3 Ninety-nine per cent (99%) of such value in interim payment certificates issued on the date of final completion and up to but excluding the final payment certificate in terms of 34.6			
31.8(A).4 One hundred per cent (100%) of such value in the final payment certificate in terms of 34.6 except where the amount certified is in favour of the employer . In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate			
Alternative B			
31.8(B) Where security as a payment reduction in terms of 14.7 has been selected, the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:			
31.8(B).1 Ninety per cent (90%) of such value in interim payment certificates issued up to the date of practical completion			
31.8(B).2 Ninety-seven per cent (97%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion			
31.8(B).3 Ninety-nine per cent (99%) of such value in interim payment certificates issued on the date of final completion and up to but excluding the final payment certificate in terms of 34.6			
31.8(B).4 One hundred per cent (100%) of such value in the final payment certificate in terms of 34.6 except where the amount certified is in favour of the employer . In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate			
Clause 31.12 is amended by deleting the following:			
Payment shall be subject to the employer giving the contractor a tax invoice for the amount due			
Fixed: Value related: Time related:	Item		
Carried to Collection		R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			F
Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1	A32.0 ADJUSTMENT TO THE CONTRACT VALUE			
	Clause 32.0			
	Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence:			
	"due to no fault of the contractor "			
	Fixed: Value related: Time related:	Item		
2	A33.0 RECOVERY OF EXPENSE AND LOSS			
	Clause 33.0			
	Fixed: Value related: Time related:	Item		
3	A34.0 FINAL ACCOUNT AND FINAL PAYMENT			
	Clause 34.0			
	Clause 34.1 is amended by removing "#" next to 34.1			
	Clause 34.2 is amended by inserting "#" next to 34.2			
	Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1"			
	Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due"			
	Fixed: Value related: Time related:	Item		
4	A35.0 PAYMENT TO OTHER PARTIES	item		
•	Clause 35.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

		1		, .	
	CANCELLATION				
1	A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT				
	Clause 36.0				
	Clause 36.1 is amended by the addition of the following clauses:				
	36.1.3 refuses or neglects to comply strictly with any of the conditions of contract				
	36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa				
	36.1.5 in the judgement of the employer , has engaged in corrupt or fraudulent practices in competing for or in executing the contract				
	Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer"				
	Clause 36.0 is amended by the addition of the following clause:				
	36.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor ; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site . The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever				
	Fixed: Value related: Time related:	Item			
2	A37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE				
	Clause 37.0				
	Clause 37.3.5 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"				
	Carried to Collection		R		
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,				
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS				

Clause 37.0 is amended by the addition of the following clause:			
37.5 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor ; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site . The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever			
Fixed: Value related: Time related:	Item		
A38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT			
Clause 38.0			
Clause 38.5.4 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"			
Clause 38.0 is amended by the addition of the following clause:			
38.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor ; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site . The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever			
Fixed: Value related: Time related:	Item		
Carried to Collection		R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1			
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1

1	A39.0 CANCELLATION - CESSATION OF THE WORKS			
	Clause 39.0			
	Clause 39.3.5 is amended by the addition of the following at the end of the sentence:			
	"within one hundred and twenty (120) working days of completion of such a report"			
	Fixed: Value related: Time related:	Item		
	DISPUTE			
2	A40.0 DISPUTE SETTLEMENT			
	Clause 40.0			
	Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years"			
	Clause 40.6 is amended by removing the reference to:			
	No clause			
	Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:			
	Whether or not mediation resolves the dispute, the parties shall bear their own costs concerning the mediation and equally share the costs of the mediator and related costs			
	Fixed: Value related: Time related:	Item		
	SUBSTITUTE PROVISIONS			
3	A41.0 STATE CLAUSES			
	Clause 41.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

	CONTRACT VARIABLES			
1	A42.0 THE SCHEDULE (DPW-04EC)			
	Clause 42.0			
	Tenderers are referred to the Contract Data DPW-04(EC) for variables pertaining to this contract			
	Fixed: Value related: Time related:	Item		
	Carried to Collection PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		R	

	SECTION B: JBCC PRELIMINARIES			
	B1.0 DEFINITIONS AND INTERPRETATION			
1	B1.1 Definitions and interpretation			
	See also clause A1.0 of Section A for additional and/or amended definitions which shall apply equally to this Section			
	Fixed: Value related: Time related:	Item		
	B2.0 DOCUMENTS			
2	B2.1 Checking of documents			
	Fixed: Value related: Time related:	Item		
3	B2.2 Provisional bills of quantities			
	Fixed: Value related: Time related:	Item		
4	B2.3 Availability of construction documentation			
	Fixed: Value related: Time related:	Item		
5	B2.4 Interests of agents			
	Fixed: Value related: Time related:	Item		
6	B2.5 Priced documents			
	Fixed: Value related: Time related:	Item		
7	B2.6 Tender submission			
	Clause 2.6 is amended by replacing "JBCC Form of Tender" with "Form of Offer and Acceptance DPW-07(EC)"			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

	<u>B3.0</u>	THE SITE			1
1	B3.1	Defined works area			1
	Fixed:_ related:	Value related: Time	Item		l
2	B3.2	Geotechnical investigation			1
	Fixed:_ related:	Value related: Time	Item		l
3	B3.3	Inspection of the site			Ì
	Fixed:_ related:	Value related: Time	Item		l
4	B3.4	Existing premises occupied			ı
	Fixed:_ related:	Value related: Time	Item		l
5	B3.5	Previous work - dimensional accuracy			1
	Fixed:_ related:	Value related: Time	Item		l
6	B3.6	Previous work - defects			ı
	Fixed:_ related:	Value related: Time	Item		Ī
7	B3.7	Services - known			1
	Fixed:_ related:	Value related: Time	Item		l
8	B3.8	Services - unknown			1
		Value related: Time	Item		l
9	B3.9	Protection of trees			ı
	Fixed:_ related:	Value related: Time	Item		l
10	B3.10	Articles of value			ı
	Fixed:_ related:	Value related: Time	Item		
		Carried to Collection		R	<u> </u>
	Bill No. PRELIN	MINARIES AND GENERAL (NOT TO BE PRICED, 1 MINARIES AND GENERAL (NOT TO BE PRICED, O JPS AND SONTSELE JSS			
					İ

1	B3.11 Inspection of adjoining properties			
	Fixed: Value related: Time related:	Item		
	B4.0 MANAGEMENT OF CONTRACT			
2	B4.1 Management of the works			
	Fixed: Value related: Time related: R	Item		
3	B4.2 Programme for the works			
	Fixed: Value related: Time related:	Item		
4	B4.3 Progress meetings			
	Fixed: Value related: Time related:	Item		
5	B4.4 Technical meetings			
	Fixed: Value related: Time related:	Item		
6	B4.5 Labour and plant records			
	Fixed: Value related: Time related:	Item		
	B5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS			
7	B5.1 Samples of materials			
	Fixed: Value related: Time related:	Item		
8	B5.2 Workmanship samples			
	Fixed: Value related: Time related:	Item		
9	B5.3 Shop drawings			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1	B5.4	Compliance	with manufacturers' instru	ctions			
	Fixed:_ related	•	_Value related:	_ Time	Item		
	B6.0	TEMPORA	RY WORKS AND PLANT				
2	B6.1	Deposits an	nd fees				
	Fixed:_ related	······································	_Value related:	_ Time	Item		
3	B6.2	Enclosure o	of the works				
	Fixed:_ related	:	_Value related: 	_ Time	Item		
4	B6.3	Advertising					
	Fixed:_ related	:	_Value related: 	_ Time	Item		
5	B6.4	Plant, equip	ment, sheds and offices				
	Fixed:_ related	·	_Value related: 	_ Time	Item		
6	B6.5	Main notice	board				
	Fixed:_ related	·	_Value related: 	_ Time	Item		
7	B6.6	Subcontrac	tors' notice board				
	Fixed:_ related	·	_Value related:	_ Time	Item		
	<u>B7.0</u>	TEMPORA	RY SERVICES				
8	B7.1	Location					
	Fixed:_ related	<u> </u>	_Value related:	_ Time	Item		
9	B7.2	Water					
	Fixed:_ related	:	_Value related: 	_ Time	Item		
			Carried to Collec	ction		R	
			ID GENERAL (NOT TO BE PI	RICED,			
		MINARIES AN	ID GENERAL (NOT TO BE PI SONTSELE JSS	RICED,			

1	B7.3	Electricity			
	Fixed:_ related	Value related: Time	Item		
2	B7.4	Telecommunication facilities			
	Fixed:_ related	Value related: Time	Item		
3	B7.5	Ablution facilities			
	Fixed:_ related	Value related: Time	Item		
	B8.0	PRIME COST AMOUNTS			
4	B8.1	Responsibility for prime cost amounts			
	Fixed:_ related	Value related: Time	Item		
		ATTENDANCE ON N/S ONTRACTORS			
5	B9.1	General attendance			
	Fixed:_ related	Value related: Time	Item		
6	B9.2	Special attendance			
	Fixed:_ related	Value related: Time	Item		
7	B9.3	Commissioning - fuel, water and electricity			
	Fixed:_ related	Value related: Time	Item		
	<u>B10.0</u>	FINANCIAL ASPECTS			
8	B10.1	Statutory taxes, duties and levies			
	Fixed:_ related	Value related: Time	Item		
		Carried to Collection		R	
		MINARIES AND GENERAL (NOT TO BE PRICED,			
		1 MINARIES AND GENERAL (NOT TO BE PRICED, LO JPS AND SONTSELE JSS			

1	B10.2 Payment for preliminaries		
	Fixed: Value related: Time related:	Item	
2	B10.3 Adjustment of preliminaries		
	Clauses B10.3.1 and B10.3.2 are amended by replacing "within fifteen (15) working days of taking possession of the site" with "when submitting his priced bills of quantities / lump sum document"		
	Fixed: Value related: Time related:	Item	
3	B10.4 Payment certificate cash flow		
	Fixed: Value related: Time related:	Item	
	B11.0 GENERAL		
4	B11.1 Protection of the works		
	Fixed: Value related: Time related:	Item	
5	B11.2 Protection / isolation of existing / sectionally occupied works		
	Fixed: Value related: Time related:	Item	
6	B11.3 Security of the works		
	Fixed: Value related: Time related:	Item	
7	B11.4 Notice before covering work		
	Fixed: Value related: Time related:	Item	
8	B11.5 Disturbance		
	Fixed: Value related: Time related:	Item	
	Carried to Collection		R
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,		
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		

1	B11.6 Environment	tal disturbance				Ì
	Fixed: related:	Value related: -	Time	Item		ľ
2	B11.7 Works clean	ing and clearing				ı
	Fixed:related:	Value related:	Time	Item		l
3	B11.8 Vermin					ı
	Fixed: related:	Value related:	Time	Item		
4	B11.9 Overhand wo	ork				ı
	Fixed: related:	Value related:	Time	Item		
5	B11.10 Instruction n	nanuals and guarantees				ı
	Fixed: related:	Value related: -	Time	Item		ĺ
6	B11.11 As built info	rmation				ı
	Fixed: related:	Value related: -	Time	Item		ľ
7	B11.12 Tenant insta	llations				ı
	Fixed:related:	Value related:	Time	Item		
	B12.0 SCHEDULE	OF VARIABLES				ı
8	B12.1 Schedule of	variables				ı
	Fixed:related:	Value related:	Time	Item		ĺ
	document and is divid categories. The pre-te in full and included in	ns all variables referred to in a led into pre-tender and post-to ender category must be comp the tender documents. Both to ender categories form part of	ender leted he			
		Carried to Collec	tion		R	Ī
		O GENERAL (NOT TO BE PR	RICED,			
	Bill No. 1 PRELIMINARIES AND GECELO JPS AND S	O GENERAL (NOT TO BE PR CONTSELE JSS	RICED,			
						Ī

"not ap choices deleted informa referen	s requiring information must be filled in, shown as applicable" or deleted and not left blank. Where is are offered, the non-applicable items are to be it. Where insufficient space is provided the ation should be annexed hereto and crossiced to the applicable clause of the schedule . The process of the schedule.		
12.1	PRE-TENDER INFORMATION		
12.1.1 <i>[</i> 2.2]	Provisional bills of quantities The quantities are provisional		
	YES		
12.1.2 [2.3]	Availability of construction documentation Construction documentation is complete		
	YES		
12.1.3 [2.4]	Interests of agents Details:		
12.1.4 [3.1]	Defined works area Details:		
12.1.5 [3.2]	Geotechnical investigation Details:		
12.1.6 <i>[3.4]</i>	Existing premises occupied Specific requirements:		
12.1.7 [3.5]	Previous work - dimensional accuracy Details:		
12.1.8 <i>[</i> 3.6]	Previous work - defects Details:		
12.1.9 <i>[</i> 3.7]	Services - known Details:		
12.1.10 [3.9]	Protection of trees Specific requirements:		
	Carried to Collection	R	
	MINARIES AND GENERAL (NOT TO BE PRICED,		
	1 MINARIES AND GENERAL (NOT TO BE PRICED, LO JPS AND SONTSELE JSS		

I	ı		1	
12.1.11 <i>Inspection of adjoining properties</i> [3.11] Specific requirements:				
12.1.12 <i>Enclosure of the works</i> [6.2] Specific requirements:				
12.1.13 Offices [6.4.3] Specific requirements: The contractor shall provide, maintain and remove on completion of the works an office for the exclusive use of the principal agent , minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times				
[6.5] Specific requirements: The contractor shall provide, erect where directed, maintain and remove on completion of the works a notice board size 3 x 3m as type Drawing GEN 063, constructed of suitable boarding with flat smooth surface and with edging bead 19mm thick round outer edges and projecting 12mm from face of boarding and rounded on front edge. The board shall be securely fixed to hoarding, where hoarding is provided, or fixed to and including a suitable supporting structure of timber or tubular posts and braces. The board is to be painted ivory white and the bead and 12mm wide dividing lines dark green as per the coat of arms for SA. All wording shall be inscribed in dark green painted sans serif lettering				
12.1.15 Subcontractors' notice board [6.6] A notice board is required				
NO Specific requirements:				
Carried to Collection		R		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS				
				ł

12.1.16 <i>Water</i> [7.2] Option A (by contractor)		
NO		
Option B (by employer - free of charge)		
NO		
Option C (by employer - metered)		
YES		
12.1.17 Electricity		
[7.3] Option A (by contractor)		
NO		
Option B (by employer - free of charge)		
NO		
Option C (by employer - metered)		
YES		
12.1.18 <i>Telecommunications</i>		
[7.4] Telephone		
YES		
Facsimile		
YES		
E-mail		
YES		
12.1.19 <i>Ablution facilities</i> [7.5] Option A (by contractor)		
YES		
Option B (by employer)		
NO		
Carried to Collection		
	R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS		
•		

١	40.4.00	Ductaction of evicting to a time the continue to the continue			ĺ
	12.1.20 works	Protection of existing/sectionally occupied			
		Protection is required			
		NO			
		Special attendance			
	[9.2]	Subcontractor (1) details:			
		Subcontractor (2) details:			
		Subcontractor (3) details:			
		Subcontractor (4) details:			
		Cabonitation (4) dotails.			
	12 1 22	Protection of the works			
		Specific requirements:			
	12.1.23	Disturbance			
	[11.5]	Specific requirements:			
		The contractor shall keep the site, structures, etc well watered during operations to prevent			
		dust and shall provide and erect and remove on			
		completion of the works all necessary			
		temporary dust screens all to the satisfaction of the principal agent			
	10 1 04	Environmental disturbance			
		Specific requirements:			
	, ,				
	12.2	POST-TENDER INFORMATION			
	12 2 1	Payment of preliminaries			
		Option A (prorated)			
		110			
		NO			
		Option B (calculated)			
		YES			
		723			
					L
		Carried to Collection	R		
					<u> </u>
	PRELIN Bill No.	IINARIES AND GENERAL (NOT TO BE PRICED,			
		IINARIES AND GENERAL (NOT TO BE PRICED,			
		O JPS AND SONTSELE JSS			
١			1	II	ı

12.2.2 [10.3]	Adjustment of preliminaries Option A (three categories)		
	NO		
	Option B (detailed breakdown)		
	YES		
12.2.3	Additional agreed preliminaries items Details:		
	Carried to Collection	R	
PRELIN	IINARIES AND GENERAL (NOT TO BE PRICED,		<u> </u>
Bill No. PRELIN	1 IINARIES AND GENERAL (NOT TO BE PRICED, O JPS AND SONTSELE JSS		
GEUEL	O JF 3 AND 30N I SELE J33		

	SECTION C: SPECIFIC PRELIMINARIES			
	Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item			
1	C1.0 CONTRACT DRAWINGS			
	* Select relevant paragraph and delete whichever is not applicable depending on whether the contract is based on a bills of quantities or lump sum document			
	* The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed			
	* A full set of drawings is issued with the tender documents indicating the full scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed			
	Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in writing from the principal agent			
	Fixed: Value related: Time related:	Item		
2	C2.0 GENERAL PREAMBLES			
	The document "Specification of Materials and Methods to be used - PW371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013)" is obtainable on the Department's website (http://www.publicworks.gov.za/ under "Consultants Guidelines"), and shall be read in conjunction with the bills of quantities / lump sum document and be referred to for the full descriptions of work to be done and materials to be used			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

1	C3.0 TRADE NAMES				
	Wherever a trade name for any product has been described in the bills of quantities / lump sum document , the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the principal agent being obtained prior to the closing date for submission of tenders				
	If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for				
	Fixed: Value related: Time related:	Item			
2	C4.0 IMPORTED MATERIALS AND EQUIPMENT				
	Where imported items are listed in the tender documents, the tenderer shall provide all the information called for, failing which the price of any such item, materials or equipment shall be excluded from currency fluctuations. (refer to Schedule of Imported Materials and Equipment DPW-23(EC) to be completed by tenderer)				
	Notwithstanding any provisions elsewhere regarding the adjustment of contract prices, the price of any item, material or equipment listed in terms of this clause shall be excluded from the Contract Price Adjustment Provisions (if applicable)				
	Fixed: Value related: Time related:	Item			
3	C5.0 VIEWING THE SITE IN SECURITY AREAS				
	The site is situated in a security area and the tenderer must arrange with the unit commander or other responsible officer to obtain permission to enter the site for tendering purposes				
	Fixed: Value related: Time related:	Item			
	Carried to Collection		R		
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1				
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS				
		1			i .

1	C6.0 COMMENCEMENT OF WORKS IN SECURITY AREAS			
	As the works falls within a security area the contractor must give the unit commander or other responsible officer notice before commencement of the works . Should the contractor fail to make such arrangements, admission to the site may be refused and any additional costs will be for the contractor's account			
	Fixed: Value related: Time related:	Item		
2	C7.0 ENTRANCE PERMITS TO SECURITY AREAS			
	As the works falls within a security area the contractor shall obtain entrance permits for his personnel and workmen entering the area and shall comply with all regulations and instructions which may be issued from time to time regarding the protection of persons and property under the control of the Defence Force, Police or chief security officer			
	Fixed: Value related:	Item		
3	C8.0 SECURITY CHECK OF PERSONNEL			
	The principal agent may require the contractor to have his personnel and workmen, or a certain number of them, security classified			
	In the event of the principal agent requesting the removal of a person or persons from the works for security reasons, the contractor shall do so forthwith and shall thereafter ensure that such person or persons are denied access to the works and the site and/or to any document or information relating to the works			
	Fixed:Value related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
	BIII No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

		ı	1	1	ı
1	C9.0 PROHIBITION ON TAKING OF PHOTOGRAPHS				
	In terms of article 119 of the Defence Act, 44 of 1957, it is prohibited to sketch or to take photographs of any military site or installation or any building or civil works thereon or to be in possession of a camera or other apparatus used for taking of photographs except when authorized thereto by or on behalf of the Minister				
	The same prohibition is also applicable to all correctional institutions in terms of article 44.1(e) of the Correctional Services Act 8 of 1959				
	Fixed: Value related: Time related:	Item			
2	C10.0 HIV/AIDS AWARENESS				
	It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document . Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained				
	The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment				
	Openia d to Callaction				
	Carried to Collection		R		
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS				

C10.1 AWARENESS CHAMPION Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS Specification Fixed:	Item		
C10.2 AWARENESS WORKSHOPS Selection and appointment of a competent Service Provider approved by the principal agent, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi- media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification Fixed:	ltem		
C10.3 POSTERS, BOOKLETS, VIDEOS, ETC. Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the construction period, all in accordance with the HIV/AIDS Specification Fixed: Value related: Time related:	ltem		
C10.4 ACCESS TO CONDOMS Provision and maintenance of condom dispensers fixed in position, including male and female condoms, replenishing male and female condoms on a daily basis as required for the duration of the construction period, all in accordance with the HIV/AIDS Specification			
Fixed:Value related: Time related:	Item		
Carried to Collection		R	
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1			
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

C10.5 MONITORING Monitoring HIV/AIDS awareness of workers, providing the principal agent with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the construction period and close out, all in accordance with the HIV/AIDS Specification Fixed:	Harra			
Time related:	Item			
C11.0 OCCUPATIONAL HEALTH AND SAFETY ACT				
The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) It is required of the contractor to thoroughly study the				
Health and Safety Specification that must be read together with and is deemed to be incorporated under				
this Section of the bills of quantities / lump sum				
document The contractor must take note that compliance with the				
Occupational Health and Safety Act, Construction				
Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-				
compliance, the principal agent, notwithstanding the				
provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing				
any progress payment certificate until the contractor				
provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of				
whatsoever nature, including interest, due to such delay				
of payment Provision for pricing of the Occupational Health and				
Safety Act, Construction Regulations and Health and Safety Specification is made under this clause and it is				
explicitly pointed out that all requirements of the				
aforementioned are deemed to be priced hereunder and no additional claims in this regard shall be entertained				
Fixed: Value related:	.,			
Time related:	Item			
		_		
Carried to Collection		R		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED,				
Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED,				
GECELO JPS AND SONTSELE JSS				
			a de la companya de	

1

1	C12.0 COVID 19 ADDITIONAL HEALTH AND SAFETY SPECIFICATION.			
	The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and the Disaster Management, 2002 (Act 57 of 2002)			
	It is required of the contractor to thoroughly study the Covid 19 Additional Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document			
	The contractor must take note that compliance with the Additional Covid 19 Occupational Health and Safety Act Requirements, Construction Regulations, Disaster Management Act and Health and Safety Specification is compulsory. In the event of partial or total noncompliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment Provision for pricing of the Additional Covid 19 Occupational Health and Safety Act Requirements, Construction Regulations, Disaster Management Act and Health and Safety Specification is made under this clause and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced hereunder and no additional claims in this regard shall be entertained The contractor is to price the Additional Covid			
	Requirements bill of quantities attached at the back of this document (C1.2 OHS bill of quantities) and carry the amount to this section of work, failure to complete the attached bill of quantities will need to non compliance.			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	PRELIMINARIES AND GENERAL (NOT TO BE PRICED,			
	Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

PRELIMINARY AND GENERAL SUMMARY : GECELO JUNIOR PRIMARY SCHOOL : CARRIED FROM LOCATION P 1 WITH THE FOLLOWING BREAKDOWN :			
FIXED :			
TIME :			
VALUE :			
TOTAL :			
NOTE: TOTAL AMOUNT TO BE CARRIED TO ITEM 1 PAGE 48 OF GECELO JUNIOR PRIMARY SCHOOL SECTION SUMMARY			
PRELIMINARY AND GENERAL SUMMARY: SONTSELE JUNIOR SECONDARY SCHOOL: CARRIED FROM LOCATION P 2 WITH THE FOLLOWING BREAKDOWN:			
FIXED :			
TIME :			
VALUE :			
TOTAL :			
NOTE: TOTAL AMOUNT TO BE CARRIED TO ITEM 1 PAGE 105 OF SONTSELE JUNIOR SECONDARY SCHOOL SECTION SUMMARY			
Carried to Collection			_
	R		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, BIII No. 1			
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS			

Section No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, P&G PRI	ED PER S	сно		
Bill No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, P&G PR	CED PER S	сно		
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	1			
	2			
	3			
	4			
	5			
	6			
	7			
	8			
	9			
	10			
	11			
	12			
	13			
	14			
	15			
	16			
	17			
	18			
Carried Forward		R		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS				

Section No. 1				1
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, P&G PRICED)	ED PER S	сно		
Bill No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, P&G PRIC	ED PER S	СНО		
COLLECTION				
	Page		Amount	
Brought Forward	No	R		
Total Brought Forward from Page No.	19			
	20			
	21			
	22			
	23			
	24			
	25			
	26			
	27			
	28			
	29			
	30			
	31			
	32			
	33			
	34			
	35			ļ
Carried Forward		R		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, Bill No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, GECELO JPS AND SONTSELE JSS				

Section No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, P&G PRIC	ED PER S	сно		
Bill No. 1				
PRELIMINARIES AND GENERAL (NOT TO BE PRICED, P&G PRIC	ED PER S	сно		
COLLECTION				
	Page No		Amount	
Brought Forward	NO	R		
Total Brought Forward from Page No.	36			
	37			
	38			
	39			
	40			
	41			
	42			
	43			
Carried to Final Summary		R		
PRELIMINARIES AND GENERAL (NOT TO BE PRICED,				
Bill No. 1 PRELIMINARIES AND GENERAL (NOT TO BE PRICED,				
GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount	
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL				
	BILL No. 01				
	PRELIMINARIES AND GENERAL				
	NOTE: SECTION NO.1 : PRELIMINARIES AND GENERAL : To be used as a pricing guide line for the requirements of each school in separate locations.				
	P1 : Gwadana Junior Secondary School				
1	The total to be carried from item Page 43 of the Preliminaries and General Section for P 1 : Gecelo Junior Primary School				
	Fixed:				
	Time:				
	Value :	Item			
	Carried Forward to Summary of Section No. 2		R		-
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 1				=
	PREMILINARIES AND GENERAL GECELO JPS AND SONTSELE JSS				
	GLOLLO UF S AND SONT SELE 333				

Item No		Quantity	Rate	Amount
3	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 02			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014).			
	Quantity breakdown			
	In this Section No. 2 of the Bills of Quantities a breakdown of the total quantities into the various buildings is indicated below each description as follows:			
	A1 - DWG 04 - Staff Ablutions C1 - DWG 06 - Grade R Ablutions D1 - DWG 14 - Male ablutions G1 - DWG 35 - Female Ablutions			
	It should be noted that due to the "rounding off" factor marginal differences can occur between the sum of the parts to the total given in the quantity column. For pricing purposes only the amount in the quantity column is to be used.			
	EARTHWORKS (PROVISIONAL)			
	Site clearance			
1	Clear the areas to be developed of all rubbish, debris, vegetation, shrubs, bush and small trees not exceeding 200mm girth and remove from site. M1:53 C1:47 D1:119 E1:0 G1:82	301		
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL			
	Bill No. 2 EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS			
	CLULLO UI O AIRD GORFIGELE GOO			

	EXCAVATIONS, FILLING, ETC.				
	BULK EXCAVATIONS				
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
1	Pit toilet. A1:6 C1:7 D1:5 E1:0 G1:21	m3	39		
	Excavate in earth exceeding 2m deep not exceeding 4m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
2	Pit toilet. A1: 25	m3	144		
	Excavations in earth of more difficult character				
3	Extra over excavations in earth for excavation in soft rock.	m3	34		
	A1:6 C1:4 D1:6 E1:0 G1:18				
4	Extra over excavations in earth for excavation in hard rock.	m3	17		
	A1:3 C1:2 D1:3 E1:0 G1:9				
	EXCAVATIONS FOR FOUNDATIONS, ETC.				
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
5	Surface trenches. A1:5 C1:4 D1:6 E1:0	m3	21		
	G1:6				
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
	Bill No. 2 EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

	Excavations in 6	earth of mor	re difficult ch	<u>naracter</u>				
1	Extra over exca rock.	vations in e	arth for exc	avation in soft	m3	4		
	A1 : 1	C1:0	D1 : 1	E1:0				
	G1 : 1							
2	Extra over exca rock.				m3	2		
	A1 : 1	C1:0	D1 : 1	E1:0				
	G1 : 1							
	Carting away of	excavated	<u>material</u>					
3	Load surplus or and cart away to Contractor.				m3	172		
	A1 : 32	C1:39	D1:33	E1:0				
	G1 : 68							
	Risk of collapse	of excavati	<u>ions</u>					
4	Allow for risk of exceeding 1.5m shoring, etc.				m2	52		
	A1 : 11	C1:11	D1:18	E1:0				
	G1 : 12							
5	Allow for risk of exceeding 1.5m shoring, etc.				m2	148		
	A1 : 31	C1:35	D1:31	E1:0				
	G1 : 51							
	Working space							
6		ing 3000mn the pit, for v lling with G7 50mm thick	n deep, 500 vaterproofin 7 imported r	naterial	m2	132		
	A1 : 35	C1:35	D1:31	E1:0				
	G1 : 31							
			Carrie	ed to Collection			R	
		- GECELO	JUNIOR PI	RIMARY SCHOOL				F
	Bill No. 2 EARTHWORKS GECELO JPS A							

	Keeping excavations free of water				
1	Allow for keeping the excavations free from water.		Item		
	Filling				
2	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	11		
	A1:2 C1:3 D1:2 E1:0				
	G1 : 4				
	Foundation courses				
3	Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc.	m3	39		
	A1:9 C1:9 D1:8 E1:0				
	G1:13				
4	50mm Thick layer of approved river sand supplied by the Contractor spread and levelled under floors, etc.	m3	2		
	A1:0 C1:0 D1:1 E1:0				
	G1 : 1				
	Compaction of surfaces				
5	Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density.	m2	157		
	A1:35 C1:28 D1:37 E1:0				
	G1:57				
6	Scarify in-situ material to a depth of 75mm and compact to 93% Mod AASHTO density.	m2	12		
	A1:3 C1:3 D1:3 E1:0 G1:3				
	Filter fabric				
7	Grade 3 needle punched non-woven synthetic fibre filter fabric laid vertically against waterproofing membrane as backfilling proceeds.	m2	198		
	A1:31 C1:51 D1:43 E1:0 G1:73				
	Comind to Collection			D	\vdash
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 2 EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

	Weedkillers, insecticides, etc.				
	Soil insecticide in accordance with SANS 5859				
1	Under floors, etc. including forming and poisoning shallow furrows against all foundation walls, filling in furrows and ramming. A1:16 C1:14 D1:37 E1:0 G1:15	m2	82		
2	To bottoms and sides of trenches.	m2	32		
	A1:12 C1:9 D1:5 E1:0 G1:6				
3	To bottoms and sides of pit excavation. A1:43 C1:51 D1:54 E1:0 G1:78	m2	226		
4	Tests Allow for Mod AASHTO density tests on filling.	No	16.00		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 2				
	EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 2				
EARTHWORKS (PROVISIONAL)				
COLLECTION				
Total Brought Forward from Page No.	Page No 48 49 50 51 52		Amount	
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 2 EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 03			
	CONCRETE, FORMWORK AND REINFORCEMENT			
	CONCRETE			
	Mass concrete 15MPa (19mm stone) in:			
1	Blinding beneath bases, strip footings, etc cast against excavated surfaces. A1:0.7 C1:0.8 D1:0.6 E1:0.0 G1:1.9	4.0		
	Reinforced concrete 25MPa (19mm stone) in:			
2	Slabs including beams and inverted beams. m3 A1:4 C1:4 D1:4 E1:0 G1:6	18		
3	Surface beds m3 A1:2 C1:1 D1:2 E1:0 G1:5	10		
4	Aprons cast in panels m3	4		
	A1:1 C1:1 D1:1 E1:0			
5	100 x 100mm Triangular fillets cast on top of pit Base Slab m	63		
	A1:11 C1:14 D1:17 E1:0 G1:21			
	Surface treatment			
6	Float surface of concrete to a wood float finish. m2 A1: 19 C1: 16 D1: 24 E1: 0	95		
	G1 : 36			
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS			

1	Powerfloating of concrete surface bed. A1:10 C1:10 D1:10 E1:0 G1:13	m2	43		
	Test blocks and testing				
2	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	No	16		
	POLYSTERENE BLOCKS ETC				
	Polystrene blocks in composite slabs				
3	850 x 500mm extreme wide at the bottom, 550mm wide at the top x 110mm high polysterene block laid end to end rows	No	72		
	PREFABRICATED CONCRETE RIB				
	25MPa precast reinforced concrete rib				
4	150 x 40mm high concrete rib with two 10mm high tensile reinforcing bars, in lengths not exceeding 5m. A1:6 C1:12 D1:9 E1:0 G1:0	m	27		
5	150 x 40mm high concrete rib with two 10mm high tensile reinforcing bars, in lengths exceeding 5m and not exceeding 7.5m.	m	27		
	A1:0 C1:0 D1:0 E1:0 G1:27				
	FORMWORK				
	Supporting bearers to prefabricated beams				
6	Bearers propped up exceeding 1,5m high and not exceeding 3.5m high A1:18 C1:18 D1:18 E1:0 G1:35	m	88		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
	Bill No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS				

	Permanent form	<u>nwork</u>						
1	Soffits of slabs in exceeding 1.5m level.	not exceedir and not exc	ng 250mm th ceeding 3.5	nick and above bearing	m2	39		
	A1:8 G1:18	C1:8	D1:5	E1:0				
	SECTION NO.2	- GECELO		d to Collection			R	
	Bill No. 3 CONCRETE, FO GECELO JPS A	ORMWORK	& REINFOR		-			

	Rough formwork	(use and w	aste) to co	ncrete to:				
	Edges, risers, er	nds and reve	<u>eals</u>					
1	Edge, riser, etc r A1 : 17 G1 : 34	not exceedir C1 : 13	ng 300mm D1 : 22	high. E1 : 0	m	86		
	<u>Openings</u>							
2	Leave or form ci through 60mm th A1:5				No	26		
	G1 : 11							
3	Leave or form so through 60mm the				No	9		
	A1 : 2 G1 : 4	C1 : 2	D1 : 1	E1:0				
4	Cut or form circuthrough 110mm				No	25		
	A1 : 5 G1 : 11	C1 : 6	D1:3	E1:0				
5	Cut or form squathrough 110mm				No	9		
	A1 : 2 G1 : 4	C1 : 2	D1 : 1	E1:0				
6	Cut or form circuthrough permane			ding 1m girth	No	25		
	A1 : 5 G1 : 11	C1 : 6	D1:3	E1:0				
7	Cut or form squa			ling 1m girth	No	0		
	through permane A1:2	ent Tormwori C1 : 2	K D1 : 1	E1:0	No	9		
	G1 : 4	01.2	51.1	21.0				
			Carrie	ed to Collection			R	
	SECTION NO.2 Bill No. 3 CONCRETE, FO GECELO JPS A	RMWORK	& REINFO	RIMARY SCHOO	_			

	Movement joints				
1	10mm Thick closed cell polyethylene joint forming material with hinged blocking piece, not exceeding 300mm wide, between concrete and concrete or brickwork surfaces.	m	86		
	A1:17 C1:13 D1:22 E1:0				
	G1:34				
2	Remove 10 x 15mm hinged blocking piece, insert polycord bond breaker and seal with an approved 2 part polysulphide sealer.	m	86		
	A1:17 C1:13 D1:22 E1:0 G1:34				
3	Slip joint not exceeding 300mm wide formed of two layers of 3 Ply malthoid laid on and including a 3:1 cement mortar bedding.	m	86		
	A1:17 C1:13 D1:22 E1:0				
	G1 : 34				
	REINFORCEMENT (PROVISIONAL)				
	<u>High tensile rod reinforcement to structural concrete</u> work				
4	16mm Diameter bars. A1: 0.107 C1: 0.076 D1: 0.141 E1: 0.000 G1: 0.058	t	0.382		
5	10mm Diameter bars. A1: 0.174 C1: 0.173 D1: 0.132 E1: 0.000 G1: 0.356	t	0.835		
	High tensile welded steel mesh reinforcement:				
6	Ref: 193 cast into concrete surfaces. A1: 19	m2	95		
7		m2	61		
7	Ref: 311 cast into concrete surfaces. A1: 12	m2	01		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
	Bill No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS				

Section No. 2		I		
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 3				
CONCRETE, FORMWORK & REINFORCEMENT				
COLLECTION				
Carried Forward to Summary of Section No. 2 SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL	Page No 54 55 56 57 58	R	Amount	
Bill No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 04			
	MASONRY			
	FOUNDATION BRICKWORK (PROVISIONAL)			
	Walls and linings in stock bricks in 5:1 cement mortar :			
1	Half brick wall. m A1:5 C1:9 D1:5 E1:0 G1:18	2 37		
2	One brick wall. A1:30 C1:24 D1:16 E1:0 G1:61	2 131		
	Reinforcement to brickwork			
3	Galvanised brick reinforcement 75mm wide built horizontally into brickwork. A1:19 C1:39 D1:19 E1:0 G1:78	m 155		
4	Galvanised brick reinforcement 150mm wide built horizontally into brickwork. A1:117 C1:94 D1:117 E1:0 G1:238	m 566		
	EXTERNAL FACE BRICKWORK			
	Allow the Prime Cost of R5 500.00 (Five Thousand Five Hundred Rand) per thousand excluding Vat for Rust Gold face bricks delivered and customer self off loaded to site, pointed with 10mm square vertical and horizontal joints			
5	Extra over ordinary brickwork for facing and pointing in stretcher bond. A1:4 C1:4 D1:5 E1:0 G1:6	2 19		
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL BIII No. 4 MANSORY GECELO JPS AND SONTSELE JSS			

	SUPERSTRUCT								
	Walls and linings	s in stock b	oricks in 5:1	cement mortar :					
1	Half brick wall. A1:8 G1:21	C1 : 5	D1 : 14	E1:0	m2	48			
2	One brick wall. A1 : 51 G1 : 70	C1 : 33	D1 : 49	E1:0	m2	203			
	Beamfilling								
3	Half brick wall. A1:6 G1:9	C1 : 5	D1 : 6	E1:0	m2	26			
	BRICKWORK S	<u>UNDRIES</u>							
	Brickwork air ver	ntilation, et	<u>:c.</u>						
4	Extra over bricky ventilation openi A1:60			120 x 85mm E1:0	No	510			
	G1 : 231								
	Reinforcement to	o brickwork	<u> </u>						
5	Galvanised brick horizontally into	brickwork.			m	169			
	A1 : 32 G1 : 76	C1 : 19	D1 : 42	E1:0					
6	Galvanised brick horizontally into		ment 150mm	n wide built	m	550			
	A1 : 146	C1:65	D1:90	E1:0					
	G1 : 249								
	<u>Bagging</u>								
7	Bag down outer cement slurry.	face of inn	er skin of br	rick wall in 4:1	m2	203			
	A1 : 51	C1 : 33	D1 : 49	E1:0					
	G1 : 70								
			Carrie			R			
	SECTION NO.2 Bill No. 4 MANSORY GECELO JPS A			RIMARY SCHOOL					
	320220 VI O A								
					I	ı		II	1

	Precast pre-stressed reinforced concrete lintols				
1	75 x 110mm Lintol not exceeding 3m long, built at both ends into brickwork over opening.	m	16		
	A1:4 C1:5 D1:2 E1:0 G1:5				
2	90 x 140mm Lintol not exceeding 3m long, built at both ends into brickwork over opening. A1:0 C1:3 D1:0 E1:0 G1:0	m	3		
	Hoop iron ties, cramps, etc.				
3	1.6 x 30mm Galvanized hoop iron roof tie 1100mm long with one end wrapped around and spiked to timber the other end built a minimum of six courses deep into brickwork as the work proceeds. A1:8 C1:11 D1:12 E1:0	No	47		
	G1:16				
4	30 x 1,2mm Galvanised hoop iron strap 800mm long shot pinned to brickwork and bent into brickwork A1:2 C1:2 D1:2 E1:0 G1:2	No	8		
	EXTERNAL FACE BRICKWORK				
	Allow the Prime Cost of R5 500.00 (Five Thousand Five Hundred Rand) per thousand excluding Vat for Rust Gold face bricks delivered and customer self off loaded to site, pointed with 10mm square vertical and horizontal joints				
5	Extra over ordinary brickwork for facing and pointing in stretcher bond. A1:55 C1:37 D1:55 E1:0 G1:79	m2	226		
	Face brick copings, lintols, cills, etc.				
6	Extra over brickwork for brick-on-edge header course tread including pointing to one face and top. A1:2 C1:3 D1:2 E1:0 G1:2	m	9		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 4 MANSORY GECELO JPS AND SONTSELE JSS				

	Brickwork air ve	entilation, et	c.					
1	Extra over brick ventilation oper pointing	work for fai	r cutting to foebrick, includ	orm 120 x 85mm ing facing and	n No	510		
	A1:60 G1:231	C1:45	D1: 174	E1:0				
	SECTION NO.2 Bill No. 4 MANSORY GECELO JPS A		JUNIOR PF	ed to Collection			R	

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 4				
MANSORY				
COLLECTION				
Total Brought Forward from Page No.	Page No 60 61 62 63		Amount	
Carried Forward to Summary of Section No. 2 SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 4 MANSORY GECELO JPS AND SONTSELE JSS		R		

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 05			
	WATERPROOFING			
	DAMP-PROOF COURSE			
	SHEET OR MEMBRANE WATERPROOFING			
	250 Micron "Gunplas USB" green polyethylene sheeting :			
1	Laid flat on prepared sand bed under solid floor. m2 A1:18 C1:20 D1:26 E1:0 G1:39	103		
	FLASHING STRIPS			
	Elastic acrylic and rubberised bitumen compound with "waterproof membrane" applied in strict accordance with the Manufacturer's instructions:			
2	Flashing strips around 110mm diameter PVC vent pipes through steel roof sheeting. A1:0 C1:0 D1:0 E1:0 G1:1	2		
	LIQUID WATERPROOFING			
	Two coats "ABE Brickseal"			
3	Vertically on bagged surface of brickwork. m2 A1:49 C1:32 D1:49 E1:0 G1:70	200		
	Carried to Collection SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 5		R	
	WATERPROOFING GECELO JPS AND SONTSELE JSS			

	MEMBRANE WATERPROOFING				
	"Duraflex" or equally approved cementitious flexible waterproofing slurry including saturation membrane with 75mm side and 100mm end laps applied in accordance with manufactures specifications				
1	Vertical surfaces of plastered brickwork. A1: 25 C1: 24 D1: 16 E1: 0	m2	110		
	G1:45 PROTECTION				
	"Abe Cote SF 356" or other equal approved epoxy tar coating on				
2	Vertical surfaces of plastered brickwork. A1: 25 C1: 24 D1: 16 E1: 0 G1: 45	m2	110		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 5 WATERPROOFING GECELO JPS AND SONTSELE JSS				

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 5				
WATERPROOFING				
COLLECTION				
Total Brought Forward from Page No.	Page No 65 66		Amount	
Carried Forward to Summary of Section No. 2		R		_
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 5 WATERPROOFING GECELO JPS AND SONTSELE JSS				_

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 06			
	ROOF COVERINGS, ETC.			
	PROFILED SHEETING OF METAL, FIBRE CEMENT, PLASTIC, ETC.			
	Metal roof sheeting			
	0,8mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face:			
1	Roof sheeting laid to a mono-pitch secured to timber purlins at approximately 940mm centres including turning up sheet at ridge and turning down sheet at eaves. m2	90		
	A1:18 C1:14 D1:25 E1:0 G1:33			
	Circular cutting			
2	Circular cutting on roof sheeting for ventilators, vent pipes, etc.	6		
	A1:0 C1:2 D1:1 E1:0 G1:3			
	Accessories, etc. to match roof sheeting			
3	Ridge capping 550mm girth.	21		
	A1:4 C1:3 D1:6 E1:0			
	G1:8			
4	Broad flute serrated closer including polyclosers.	21		
	A1:4 C1:3 D1:6 E1:0 G1:8			
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL			
	Bill No. 6 ROOF COVERINGS, ETC GECELO JPS AND SONTSELE JSS			

1	Narrow flute serrated closer including polyclosers.				m	21		
	A1:4	C1:3	D1:6	E1:0				
	G1 : 8							
2	Ridge finial.				No	8		
	A1 : 2	C1:2	D1:2	E1:0				
	G1 : 2							
			Carrie	ed to Collection			R	
								
	SECTION NO.2 Bill No. 6	- GECELO	JUNIOR PF	RIMARY SCHOOL	-			
	ROOF COVERI							
	GECELO JPS A	AND SONTS	SELE JSS					

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 6				
ROOF COVERINGS, ETC				
COLLECTION				
Total Brought Forward from Page No.	Page No 68 69		Amount	
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 6 ROOF COVERINGS, ETC GECELO JPS AND SONTSELE JSS		K		_

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 07			
	CARPENTRY AND JOINERY			
	CARPENTRY			
	PLATE NAILED TIMBER ROOF CONSTRUCTION			
	Fixing:			
	All nailing of timber roof rafters, purlins, etc shall be done with galvanised nails. In coastal areas, copper, aluminium or stainless steel nails shall be used.			
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to blockwork or concrete.			
	Erection certificates			
1	Contractor is to supply a roof rafters erection certificate for the building stating that the erection and installation of the roof rafters has been inspected and approved by a professional registered structural engineer.	4		
	A1:1 C1:1 D1:1 E1:0			
	G1 : 1			
	Purlins, bracing, etc.			
	Sawn softwood :			
2	38 x 114mm Wall plate wired down (wire ties elsewhere).	63		
	A1 : 9			
2		110		
3	50 x 76mm Purlins. m A1:22 C1:17 D1:31 E1:0	110		
	G1:40			
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 7			
	CARPENTRY AND JOINERY GECELO JPS AND SONTSELE JSS			
		•		•

1	76 x 38mm S5 Trea	ted Timl	ber		m	28			
	A1 : 6 (G1 : 11	C1 : 5	D1:6	E1:0					
2	38 x 38 x 152mm Lo	ong clea	•	rafter foot.	No	34			
	A1 : 8 G1 : 16	C1 : 4	D1 : 6	E1:0					
3	50 x 76 x 500mm Lo A1 : 10 C G1 : 10	ong spro 1 : 10	ocket spiked D1 : 10	I to timber purlin. E1 : 0	No	40			
	Laminated S. A. Pin	<u>e</u>							
4	152 x 38mm S5 Tim	nber Raf	ters		m	86			
	A1 : 15 C	1 : 15	D1 : 24	E1:0					
	Sundries:								
5	Hurricane clip fixed	to purlin	and rafter.		No	110			
	A1 : 20 C	1 : 20	D1:30	E1:0					
	<u>JOINERY</u>								
	Plastic, fibre cement	t, etc.							
	Pressed fibre-cemer	nt:							
6	12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc.				m	21			
	A1 : 4 G1 : 8	C1 : 3	D1 : 6	E1:0					
7	80 x 275mm Barge timber rafter includir strips, etc.				m	32			
	A1 : 8 G1 : 8	C1 : 8	D1:8	E1:0					
			Carrie	ed to Collection			R		
	SECTION NO.2 - GI Bill No. 7 CARPENTRY AND GECELO JPS AND	JOINER	Υ	RIMARY SCHOOL					
							I	I	

	TIMBER DOORS, WINDOWS ETC.				
	Wrot hardwood :				
1	44mm Thick framed, ledged, braced and battened door, size 762 x 1000mm high, comprising 44 x 180mm stiles and top rail, 22 x 180mm bottom rail and diagonal brace and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths. A1:0 C1:3 D1:0 E1:0	o 3	3		
	Frames and linings				
	Wrot hardwood :				
2	38 x 100mm Meranti jamb lining bolted to brickwork with and including 10 x 140mm masonry anchors at approximately 600mm centres. A1:0 C1:4 D1:0 E1:0	m 4	ŀ		
	G1:0				
	Openite ditta Oplilla etta e				
	Carried to Collection		R		
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 7				
	CARPENTRY AND JOINERY GECELO JPS AND SONTSELE JSS				

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 7				
CARPENTRY AND JOINERY				
COLLECTION				
Total Brought Forward from Page No.	Page No 71 72 73		Amount	
Carried Forward to Summary of Section No. 2		R R		
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 7 CARPENTRY AND JOINERY GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 08			
	IRONMONGERY			
	IRONMONGERY TO TIMBER			
	<u>Hinges</u>			
1	100 x 75mm Heavy duty brass butt hinges. No A1:0 C1:6 D1:0 E1:0 G1:0	6		
	<u>Handles</u>			
2	100mm Chromium plated pull handle. No A1:0 C1:3 D1:0 E1:0 G1:0	3		
	IRONMONGERY TO METALWORK			
	Locksets, etc. provided with two keys and to be masterkeyed			
3	51mm brass padlock with stainless steel shackle. No A1:2 C1:1 D1:2 E1:0 G1:1	6		
	IRONMONGERY FIXED TO CONCRETE, TILING, ETC.			
	Push plates, kicking plates, indicator plates, etc.			
4	152 x 152 x 3mm Thick anodised silver aluminium sex indicator plate. A1:2 C1:1 D1:2 E1:0	6		
	G1 : 1			
5	152 x 152 x 3mm Thick anodised silver aluminium disabled indicator plate.) 1		
	A1:0 C1:0 D1:0 E1:0 G1:1			
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL BIII No. 8 IRONMONGERY GECELO JPS AND SONTSELE JSS			

	3mm Thick x 32mm high c painted numerals or letters steel door frame	lear perspex , countersun	signs with white k tap screwed to				
1	Sign with "MALE STAFF" 6 A1:1 C1:0 G1:0	enscribed. D1 : 0	E1:0	No	1		
2	Sign with "FEMALE STAFF A1:1 C1:0 G1:0	=" enscribed. D1 : 0	E1:0	No	1		
	Door stops						
3	Black rubber door stop plue A1:3 C1:3 G1:6	gged to wall. D1 : 2	E1:0	No	14		
	<u>Sundries</u>						
4	50mm Plastic key tag. A1:2 C1:1	D1 : 2	E1:0	No	7		
		Carrie	d to Collection			R	_
	SECTION NO.2 - GECELO Bill No. 8 IRONMONGERY GECELO JPS AND SONT		RIMARY SCHOOL	-			

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 8				
IRONMONGERY				
COLLECTION				
Total Brought Forward from Page No.	Page No 75 76		Amount	
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL BIII No. 8 IRONMONGERY GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount	
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL				
	BILL No. 09 STRUCTURAL STEEL Pre-galvanised (Z450) structural steelwork (Grade 350W)				
1	100 x 50 x 20 x 2mm Cold formed lipped channel including bolting to brickwork at 910mm centres. A1:2 C1:0 D1:2 E1:0 G1:5	9			
	Carried Forward to Summary of Section No. 2		R		
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 9 STRUCTURAL STEEL GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 10			
	<u>METALWORK</u>			
	Hot dipped galvanised mild steel gates			
1	Single gate, size 900mm wide x 2050mm high, the leaf formed of 25 x 25 x 2mm wall thickness mild steel pipe framing all round and two horizontal intermediate rails with mitred and welded angles, the gate filled in with 12mm diameter mild steel bars welded, at each end, vertically to perimeter and intermediate framing at not exceeding 109mm centres, the leaf fitted with a 150mm long padbolt, the leaf to receive hasp and staple formed of 40 x 6mm mild steel flat bar welded onto frames and including fitting with two 50 x 10mm flat bar tee brackets and 16mm round bar pin hinges, twice bolted to wall with and including M16 x 95mm galvanised coach screws.	6		
	G1 : 1			
2	Hot dipped galvanised mild steel mesh screen Mesh screen, size 2230mm wide x 2100mm high, formed of 32 x 32 x 2mm wall thickness square hollow section framing all round and two horizontal rails with mitred and welded angles, the framing covered with 50 x			
	50 x 4mm weld mesh tack welded on, and including fitting with two 50 x 10mm flat bar tee brackets and 16mm round bar pin hinges, twice bolted to wall with and including M16 x 95mm galvanised coach screws.	1		
	A1:0 C1:1 D1:0 E1:0 G1:0			
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 10 METALWORK GECELO JPS AND SONTSELE JSS			

1		ì	1		1
	Hot dipped galvanised steel cladded doors and accessories				
1	Door, size 760 x 1680mm high, formed of 19 x 19mm tubular steel perimeter framing and horizontal middle rail welded at angles and intersections, covered on one side with 0,6mm galvanised sheeting, prepainted "Golden Brown", pressed to shape with edges lapped around and rivetted to frame at 300mm centres, with slot for and including barrel bolt, the gate fitted with and including 25mm diameter x 2120mm long pivot pipe support welded on, 150 x 38 x 3mm top bearing bolted to beam with 2 x 6mm diameter bolts, including top cap bearing bush, washers, bottom bearing bush and finishing smooth on all exposed edges, complete with all fixing brackets, bolts etc. A1:3 C1:0 D1:2 E1:0 G1:6 Pre-galvanised steel chawl doors	No	11		
2	Single door to suit one brick wall, size 950 x 2030mm high, provided complete with integral frame,				
	ironmongery, etc. finished with red oxide primer to receive paint (elsewhere). A1:0 C1:0 D1:0 E1:0 G1:1	No	1		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 10 METALWORK GECELO JPS AND SONTSELE JSS				

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 10				
METALWORK				
COLLECTION				
Total Brought Forward from Page No.	Page No 79 80		Amount	
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 10 METALWORK GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
1	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 11			
	PLASTERING			
	SCREEDS			
	Untinted granolithic screeds, etc. mixed by volume 4 parts granite chips, 1 part sand and 2 parts cement			
1	40mm Thick screed to floors and landings. A1: 11	2 51		
2	25mm Thick screed to falls A1:3 C1:3 D1:2 E1:0 G1:7	2 15		
	<u>Skirtings</u>			
3	75mm High coved skirting. A1: 18	m 107		
	PLASTER			
	One coat internal 1:4 cement plaster on :			
4	Brick walls in pit. A1:39 C1:32 D1:25 E1:0	2 209		
5	Brick walls (ICP) m A1: 76	2 283		
	Carried Forward to Summary of Section No. 2 SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 11 PLASTERING GECELO JPS AND SONTSELE JSS		R	

Item No			Quantity	Rate	Amount	
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL					
	BILL No. 12					
	PLUMBING AND DRAINAGE (PROVISIONAL)					
	Roof gutters, rainwater pipes, etc.					
	uPVC gutter including gutter brackets					
1	125mm Half round eaves gutters on gutter brackets at 1000mm centres maximum fixed to fascias.	m	21			
	A1:4 C1:3 D1:6 E1:0					
	G1 : 8					
2	Extra over uPVC gutter for forming discharge outlet to suit 100 x 75mm downpipe.	No	4			
	A1:1 C1:1 D1:1 E1:0 G1:1					
3	Extra over gutter for stopped end.	No	8			
ŭ	A1:2 C1:2 D1:2 E1:0	.10				
	G1:2					
4	75mm Rainwater downpipe fixed to wall with and including proprietary holderbats.	m	14			
	A1:2 C1:4 D1:4 E1:0 G1:4					
5	Extra over rainwater downpipe for bend.	No	8			
	A1:2 C1:2 D1:2 E1:0 G1:2					
	Carried to Collection			R		
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 12					
	PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS					

	PIPEWORK, ETC.				
	Pipes, pipe fittings, etc.				
	WATER SUPPLIES				
	Class 6 HDPE waterpipe				
1	22mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc. A1:0 C1:0 D1:0 E1:0 G1:12	m	12		
	Extra over Class 6 HDPE pipe for fittings				
2	22mm Fittings. A1:0 C1:0 D1:0 E1:0 G1:10	No	10		
	Class 2 copper pipes with straight compression fittings				
3	15mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc. A1:2 C1:0 D1:10 E1:0	m	12		
	G1:0				
	Extra over copper pipes for brass compression fittings				
4	15mm Fittings.	No	14		
	A1:4 C1:0 D1:10 E1:0 G1:0				
	Extra over copper pipes for capillary fittings with				
	soldered joints				
5	15mm Fittings. A1:2 C1:0 D1:4 E1:0 G1:0	No	6		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 12 PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

	SOIL DRAINAG	<u>E</u>						
	uPVC Pipes witl	h solvent we	elded straig	ht joints :				
1	40mm Pipes. A1 : 1 G1 : 0	C1:0	D1 : 4	E1:0	m	5		
2	50mm Pipes. A1 : 1 G1 : 0	C1:0	D1:4	E1:0	m	5		
	White uPVC ver	nt pipe in sir	ngle lengths	<u>s :</u>				
3	brackets at not e			Il with proprietary res. E1:0	m	60		
	G1 : 28							
	Extra over uPV0	C pipes for s	solvent weld	<u>ded fittings :</u>				
4	40mm Plain ber	nd. C1 : 0	D1:8	E1:0	No	10		
	G1:0	CI.U	D1.6	E1.0				
5	50mm Plain ber	nd.			No	4		
	A1 : 2	C1:0	D1:2	E1:0				
	G1:0							
6	Black PVC whirl pipe.	lybird vent c	apping ove	r the 110mm vent	No	15		
	A1 : 3 G1 : 7	C1 : 3	D1 : 2	E1:0				
	Inspection cha	mbers, cate	ch pits, etc	<u>.</u>				
	Light Composite	covers and	frames					
7	screws lock fast holes designed	and frame in en cover wi for the easy	nclusive of to th frame and r lifting and	two stainless steel and two vented	No	9		
			Carrie	ed to Collection			R	
	SECTION NO.2 Bill No. 12 PLUMBING AND GECELO JPS A	D DRAINAG	SE (PROVIS	RIMARY SCHOOL SIONAL)				

	SANITARY FITT	INGS, TAN	IKS, GEYS	ERS, ETC.				
	Plastic sanitaryw	<u>rare</u>						
1	"Atlas Plastics 23 with integral flap including 6 x 75r A1:3 G1:7	four times	olugged to		No	15		
2	"Atlas Plastics 50 "496AP" waterles and including pro	ss urinal wa	ste fitting h		No	5		
3	G1:0 "Atlas Plastics C 245mm, provided in soap holder, h proprietary wall b A1:0 G1:1 Sanitary fitting st	d complete ung on wall orackets. C1:0	with two ta	pholes and built	No	1		
4	Satin chrome thic 71, plugged to w A1:3		et roll holde D1 : 2	er, PWD Sample	No	15		
5	G1:7 Heavy-duty doub A1:3 G1:7	ole-flap hing C1 : 3	ed toilet se D1 : 2	eat and cover. E1:0	No	15		
7	to wall with and i A1:0 G1:1 Dog leg grab rail wall with and inc	m long with including sta C1:0 with three luding stain	two flange: ainless stee D1:0 flanges "DL less steel s	E1:0 .3" plugged to crews.	No No	1		
	A1:0 G1:1 SECTION NO.2-Bill No. 12 PLUMBING AND GECELO JPS A	DRAINAG	JUNIOR PI E (PROVIS	ed to Collection RIMARY SCHOOL SIONAL)			R	

	Tanks, geysers, etc. Rainwater tanks				
1	2500 Litre polyethylene rotomoulded vertical water storage tank complete, on 1600 x 1600 tank stand, including lid, fitted with and including 50 x 15mm reducer and setting in position on concrete tankstand (elsewhere measured) and tying down with 4mm diameter galvanised wire wrapped twice around centre of tank and secured to each corner of tank stand with double strand of 4mm diameter galvanised wire embedded into concrete. (Note: tanks to be filled with water before Practical Completion).	a	4		
	G1 : 1 Galvanised Steel Pipe				
2	22mm galvanised steel pipe A1:1 C1:1 D1:1 E1:0 G1:1	m	4		
	Taps, valves, etc.				
	Solid cast brass taps, valves, etc.				
3	"Cobra KM2-200" or other equal approved 15mm chrome plated metered bib tap with non-hold open feature and flow controller.	No	1		
	A1:0 C1:0 D1:0 E1:0 G1:1				
4	15mm Ball-o-stop valve.	No	5		
	A1:1 C1:0 D1:4 E1:0 G1:0				
5	22mm Gate valve	No	4		
	A1:1 C1:1 D1:1 E1:0 G1:1				
6	22mm Non Return valve	No	4		
	A1:1 C1:1 D1:1 E1:0 G1:1				
	Carried to Collection	n		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHO Bill No. 12 PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS	OOL			

	Waste unions, tra	aps, etc.						
	Outlets, traps, et	<u>c:</u>						
1	50mm Chromium A1 : 1 G1 : 0	n plated PV C1 : 0	C urinal bo	ttle trap. E1 : 0	No	5		
2	38mm Chromiun with plug, chain a	n plated bra and chain s C1:0	ass slotted b stay. D1 : 0	pasin waste outle	et No	1		
	G1:1	C1.U	Ы.0	E1.0				
3	38mm PVC Mini A1:0 G1:1	P-trap. C1:0	D1:0	E1:0	No	1		
			Carrie	ed to Collection			R	
	SECTION NO.2 - Bill No. 12 PLUMBING AND GECELO JPS A	DRAINAG	SE (PROVIS		DL			

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 12				
PLUMBING AND DRAINAGE (PROVISIONAL)				
COLLECTION				
Total Brought Forward from Page No.	Page No 83 84 85 86 87 88		Amount	
Carried Forward to Summary of Section No. 2 SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 12 PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS		R		

Item No		Quantity	Rate	Amount
	SECTION No. 2 - GECELO JUNIOR PRIMARY SCHOOL			
	BILL No. 13			
	PAINTWORK			
	PAINT ON CONCRETE, PLASTER, ETC			
	Prepare and apply one coat plaster primer, one coat universal undercoat and two coats "Wall & All" or other equal approved washable suede sheen acrylic PVA paint on:			
1	Internal smooth plastered walls. m2	330		
	A1 : 76 C1 : 53 D1 : 74 E1 : 0 G1 : 127			
2	Internal smooth plastered wall in narrow widths not exceeding 300mm wide m2	3		
	A1:0 C1:0 D1:1 E1:0 G1:1			
	Scrub surface with degreaser, rinse thoroughly with tap water, and apply one coat sealer and two coats epoxy paint on:			
3	Concrete floated or screeded floors m2	51		
	A1:11 C1:6 D1:17 E1:0 G1:17			
4	Granolithic skirting not exceeding 300mm girth.	115		
	A1 : 20 C1 : 19 D1 : 29 E1 : 0 G1 : 47			
	PAINT ON TIMBER			
	Prime or oil			
5	Backs of frames or linings not exceeding 300mm girth. m A1:0 C1:7 D1:0 E1:0	7		
	G1:0			
	Carried to Collection		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL BIII No. 13 PAINTWORK GECELO JPS AND SONTSELE JSS			

1	Doors A1:0 G1:0	C1:5	D1:0	E1:0	m2	5		
	PAINT ON METAL Prepare and apply		oituminous p	paint on :				
2	Backs of steel doo A1:0 G1:2		D1:0	E1:0	m2	2		
	One coat steel etcl undercoat and two							
3	Hot dipped galvani A1 : 4 G1 : 2	ised steel g C1:2	pates. D1 : 4	E1:0	m2	12		
4	Hot dipped galvani A1:0 G1:0	ised steel n	nesh screer D1:0	ns. E1:0	m2	5		
	One coat red oxide and two coats glos			ersal undercoat				
5	Pre-galvanised ste A1:0 G1:2	el doors. C1:0	D1:0	E1:0	m2	2		
6	Pre-galvanised ste A1:0 G1:2	el door frai C1 : 0	mes. D1:0	E1:0	m2	2		
	PAINT ON FIBRE- Prepare and apply		olaster prime	er and two				
7	External fibre ceme cover strips. A1:1 G1:2			luding priming E1 : 0	m2	5		
	SECTION NO.2 - 0 Bill No. 13 PAINTWORK GECELO JPS ANI		JNIOR PRII	to Collection MARY SCHOOL			R	

1	External fibre ce cover strips.	ment barge	eboard inclu	ding priming	m2	8		
	A1 : 2 G1 : 2	C1 : 2	D1 : 2	E1:0				
	PAINT ON PVC							
	Prepare and app	oly two coat	s black PV	A paint on:				
2	Vent pipes. A1:1 G1:3	C1 : 1	D1:1	E1:0	m2	6		
				ed to Collection			R	
	SECTION NO.2 Bill No. 13 PAINTWORK GECELO JPS A			RIMARY SCHOO)L			

Section No. 2	1			
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 13				
PAINTWORK				
COLLECTION				
<u>GOLLETION</u>	Page		Amount	
Total Brought Forward from Page No.	90 91 92		7.1110411	·
Carried Forward to Summary of Section No. 2		R		_
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 13 PAINTWORK GECELO JPS AND SONTSELE JSS				=

Item No			Quantity	Rate	Amount	
1	SECTION No. 2 - EXTERNAL WORKS - GECELO JUNIOR PRIMARY SCHOOL					
	BILL No. 14					
	EXTERNAL WORKS (PROVISIONAL)					
	Note:					
	For Preambles see "PW 371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013).					
	DEMOLITIONS					
	<u>Demolitions</u>					
	Brickwork building structures					
1	Demolish and cart away single storey toilet block complete, size on plan 10000mm long x 4000mm wide x approximately 3000mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, with plastered and painted block walls with timber doors, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	No	1			
	<u>Pit toilets</u>					
2	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out.	No	1			
	Carried to Collection			R		_
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS					=

1	Allow for breaking down and removing from site entire pit latrine structure including any structure that may be inside the pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured). Backfill existing hole with imported filling in max 150mm layers and compact to 95% MOD AASHTO density. THE FOLLOWING IN WALKWAYS, RAMPS, ETC. EARTHWORKS	No	1		
	Site clearance				
2	Clear the areas to be developed of all rubbish, debris, vegetation, shrubs, bush and small trees not exceeding 200mm girth and remove from site.	m2	120		
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
3	Reduced levels under solid floors.	m3	24		
	Carting away of excavated material				
4	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	24		
	Filling				
5	150mm G7 Sub-base course, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 93% modified AASHTO density under slabs.	m3	18		
	Prescribed Testing				
6	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.	No	2		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	Reinforced concrete 25MPa (19mm stone) in:				
1	Paving in panels including any necessary formwork.	m3	12		
2	Ramps.	m3	0.4		
	Surface treatment				
3	Float surface of concrete to a wood float finish.	m2	120		
	Test blocks and testing				
4	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	No	2		
	Movement joints				
5	10mm Thick "Jointex" closed cell polyethylene joint filler with hinged blocking piece between concrete surfaces not exceeding 300mm wide.	m	33		
6	Remove hinged blocking piece and fill 10 x 15mm cavity with an approved 2 part polysulphide sealer.	m	33		
	<u>FORMWORK</u>				
	Edges, risers, ends and reveals				
7	Edge, riser, etc not exceeding 300mm high.	m	200		
	Reinforcement				
8	Ref: 193 High tensile welded steel mesh reinforcement cast into concrete surfaces.	m2	120		
	THE FOLLOWING IN STORMWATER CUT OFF DRAIN / EARTH BERM				
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
9	Reduced levels	m3	30		
	Carried to Collection			R	\vdash
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
	Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	Filling				
1	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	30		
	Compaction of surfaces				
2	Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density.	m2	60		
	Grassing, ground cover, etc.				
3	Kikuyu turf (sods or rolls) instant lawn 25 to 40mm thick, imported from commercial sources, laid firmly with staggered joints within three days of being lifted.	m2	50		
	THE FOLLOWING IN CONCRETE CHANNELS, ETC.				
	<u>EARTHWORKS</u>				
4	Holes	m3	0.3		
5	Surface trenches.	m3	1		
	Carting away of excavated material				
6	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	1		
7	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	1		
	<u>Sundries</u>				
8	Rip prepared platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	3		
					_
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 14				
	EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	Prescribed Testing				
1	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.	No	4		
	<u>FORMWORK</u>				
	Edges, risers, ends and reveals				
2	Edge, riser, etc not exceeding 300mm high.	m	6		
	Grooves, channels, mortices, etc.				
3	700 x 150mm V-Channels in top	m	3		
4	1500 x 750 x 150mm Concrete V-Channel Spreader	No	1		
	REINFORCEMENT (PROVISIONAL)				
	High tensile rod reinforcement to structural concrete work				
5	12mm Diameter bars.	t	0.007		
	Reinforcement				
6	Ref: 193 High tensile welded steel mesh reinforcement cast into concrete surfaces.	m2	3		
	THE FOLLOWING IN STAND PIPE BIP TAP ETC.				
	<u>EARTHWORKS</u>				
7	Holes	m3	1		
8	Surface trenches.	m3	6		
	Carting away of excavated material				
9	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	1		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	Risk of collapse of excavations				
1	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	7		
	Keeping excavations free of water				
2	Allow for keeping the excavations free from water.		Item		
	<u>Filling</u>				
3	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	6		
	Foundation courses				
4	Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc.	m3	0.3		
	Sundries				
5	Rip prepared platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	2		
	Prescribed Testing				
6	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.	No	2		
	CONCRETE (Labour intensive)				
	Mass concrete 25MPa (19mm stone) in:				
7	Strip foundations cast against excavated surfaces.	m3	2		
	Reinforced concrete 25MPa (19mm stone) in:				
8	Slabs	m3	1		
	Carried to Collection			R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				
		1	ı	· ·	 •

_
+

Section No. 2				
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
Bill No. 14				
EXTERNAL WORKS				
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	94			
	95			
	96			
	97			
	98			
	99			
	100			
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				
				l

	Section No. 2			
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL			
	SECTION SUMMARY - SECTION NO.2 - GECELO JUNIOR PRIMA	RY SCHOO	<u> </u>	
Bill No		Page No		Amount
1	PREMILINARIES AND GENERAL	47		
2	EARTHWORKS (PROVISIONAL)	53		
3	CONCRETE, FORMWORK & REINFORCEMENT	59		
4	MANSORY	64		
5	WATERPROOFING	67		
6	ROOF COVERINGS, ETC	70		
7	CARPENTRY AND JOINERY	74		
8	IRONMONGERY	77		
9	STRUCTURAL STEEL	78		
10	METALWORK	81		
11	PLASTERING	82		
12	PLUMBING AND DRAINAGE (PROVISIONAL)	89		
13	PAINTWORK	93		
14	EXTERNAL WORKS	101		
	Sub-Total		R	
	Carried Forward		R	
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL Bill No. 14			
	EXTERNAL WORKS GECELO JPS AND SONTSELE JSS			

	Section No. 2				
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
	SECTION SUMMARY - SECTION NO.2 - GECELO JUNIOR PRIMA	RY SCHOO	<u> </u>		
Bill No		Page No		Amount	
110	Brought Forward	140	R		
	CONTINGENCY PROVISIONS				
	The Tenderer is to allow hereunder for 5 (Five) percent of the Nett Builders Work Sub-Total to be used as a Budgetary Provision for construction contingencies of a general nature and for the finalisation of design detailing. This sum, or any portion thereof, shall be expended at the sole discretion of the Principal Agent. Any residual balance remaining subsequent to such expenditure shall be deducted in its entirety from the Contract Sum.	%			
	Carried to Final Summary		R		
	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL				
	GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 01			
	PRELIMINARIES AND GENERAL			
	NOTE: SECTION NO.1 : PRELIMINARIES AND GENERAL : To be used as a pricing guide line for the requirements of each school in separate locations.			
	P2 : Mavata Junior Secondary School			
1	The total to be carried from item Page 43 of the Preliminaries and General Section for P 2 : Sontsele Junior Secondary School			
	Fixed:			
	Time:			
	Value :	Item		
	Carried Forward to Summary of Section No. 3		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 1			
	PREMILINARIES AND GENERAL GECELO JPS AND SONTSELE JSS			

Item No		Quantity	Rate	Amount
1	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 02			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014).			
	Quantity breakdown			
	In this Section No. 3 of the Bills of Quantities a breakdown of the total quantities into the various buildings is indicated below each description as follows:			
	A1 - DWG 04 - Staff Ablutions C1 - DWG 06 - Grade R Ablutions D1 - DWG 14 - Male ablutions G1 - DWG 35 - Female Ablutions			
	It should be noted that due to the "rounding off" factor marginal differences can occur between the sum of the parts to the total given in the quantity column. For pricing purposes only the amount in the quantity column is to be used.			
	EARTHWORKS (PROVISIONAL)			
	Site clearance			
1	Clear the areas to be developed of all rubbish, debris, vegetation, shrubs, bush and small trees not exceeding 200mm girth and remove from site. M1:53 C1:47 D1:119 E1:0 G1:82	301		
	Openity I to Openity I			
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 2 EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS			

	EXCAVATIONS, FILLING, ETC.				
	BULK EXCAVATIONS				
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
1	Pit toilet. A1:6 C1:7 D1:5 E1:0 G1:21	m3	39		
	Excavate in earth exceeding 2m deep not exceeding 4m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
2	Pit toilet. A1: 25 C1: 32 D1: 25 E1: 0 G1: 62	m3	144		
	Excavations in earth of more difficult character				
3	Extra over excavations in earth for excavation in soft rock.	m3	34		
	A1:6 C1:4 D1:6 E1:0 G1:18				
4	Extra over excavations in earth for excavation in hard rock.	m3	17		
	A1:3 C1:2 D1:3 E1:0 G1:9				
	EXCAVATIONS FOR FOUNDATIONS, ETC.				
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
5	Surface trenches.	m3	21		
	A1:5 C1:4 D1:6 E1:0 G1:6				
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 2 EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

	Excavations in e	earth of moi	e difficult cl	<u>haracter</u>				
1	Extra over exca rock.	vations in e	arth for exc	avation in soft	m3	4		
	A1 : 1	C1:0	D1 : 1	E1:0				
	G1 : 1							
2	Extra over exca rock.	vations in e	arth for exc	avation in hard	m3	2		
	A1 : 1	C1:0	D1 : 1	E1:0				
	G1 : 1							
	Carting away of	<u>excavated</u>	<u>material</u>					
3	Load surplus or and cart away to Contractor.				m3	172		
	A1 : 32	C1:39	D1:33	E1:0				
	G1 : 68							
	Risk of collapse	of excavati	<u>ons</u>					
4	Allow for risk of exceeding 1.5m shoring, etc.	n deep inclu	ding all nec	essary timber	m2	52		
	A1 : 11	C1 : 11	D1 : 18	E1:0				
	G1 : 12							
5	Allow for risk of exceeding 1.5m shoring, etc.	n deep inclu	ding all nec	essary timber	m2	148		
	A1 : 31	C1 : 35	D1 : 31	E1:0				
	G1 : 51							
	Working space							
6		ing 3000mn the pit, for v Iling with G7 50mm thick	n deep, 500 vaterproofin 7 imported r	material	m2	132		
	A1 : 35	C1 : 35	D1:31	E1:0				
	G1 : 31							
			0	ad ta Oalla atlan				_
			Carri	ed to Collection			R	
	SECTION NO.3 Bill No. 2	- SONTSE	LE JUNIOR	SECONDARY SC				
	EARTHWORKS	(PROVISIO	ONAL)					
	GECELO JPS	•						

	Keeping excavations free of water				
1	Allow for keeping the excavations free from water.		Item		1
	Filling				Ì
2	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density. A1:2 C1:3 D1:2 E1:0 G1:4	m3	11		
	Foundation courses				1
3	Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc. A1:9 C1:9 D1:8 E1:0 G1:13	m3	39		
4	50mm Thick layer of approved river sand supplied by the Contractor spread and levelled under floors, etc. A1:0 C1:0 D1:1 E1:0 G1:1	m3	2		
	Compaction of surfaces				1
5	Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density. A1: 35 C1: 28 D1: 37 E1: 0 G1: 57	m2	157		
7	Scarify in-situ material to a depth of 75mm and compact to 93% Mod AASHTO density. A1:3 C1:3 D1:3 E1:0 G1:3 Filter fabric Grade 3 needle punched non-woven synthetic fibre filter	m2	12		
	fabric laid vertically against waterproofing membrane as backfilling proceeds. A1:31 C1:51 D1:43 E1:0 G1:73	m2	198		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 2 EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				-

	Weedkillers, insecticides, etc.				
	Soil insecticide in accordance with SANS 5859				
1	Under floors, etc. including forming and poisoning shallow furrows against all foundation walls, filling in furrows and ramming. A1: 16 C1: 14 D1: 37 E1: 0 G1: 15	m2	82		
2	To bottoms and sides of trenches.	m2	32		
_	A1:12 C1:9 D1:5 E1:0				
3	To bottoms and sides of pit excavation. A1:43 C1:51 D1:54 E1:0 G1:78	m2	226		
4	Tests Allow for Mod AASHTO density tests on filling.	No	16.00		
	Carried to Collection			R	
					<u> </u>
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 2				
	EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 2				
EARTHWORKS (PROVISIONAL)				
COLLECTION				
Total Brought Forward from Page No.	Page No 105 106 107 108 109		Amount	
Carried Forward to Summary of Section No. 3		R		
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 2				_
EARTHWORKS (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 03			
	CONCRETE, FORMWORK AND REINFORCEMENT			
	CONCRETE			
	Mass concrete 15MPa (19mm stone) in:			
1	Blinding beneath bases, strip footings, etc cast against excavated surfaces. m3	4.0		
	A1:0.7 C1:0.8 D1:0.6 E1:0.0 G1:1.9			
	Reinforced concrete 25MPa (19mm stone) in:			
2		18		
2	Slabs including beams and inverted beams. m3 A1:4 C1:4 D1:4 E1:0 G1:6	10		
3	Surface beds m3 A1:2 C1:1 D1:2 E1:0 G1:5	10		
4	Aprons cast in panels m3	4		
	A1:1 C1:1 D1:1 E1:0			
5	100 x 100mm Triangular fillets cast on top of pit Base Slab m	63		
	A1:11 C1:14 D1:17 E1:0 G1:21			
	Surface treatment			
6	Float surface of concrete to a wood float finish. m2 A1:19 C1:16 D1:24 E1:0 G1:36	95		
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS			

1	Powerfloating of concrete surface bed. A1:10 C1:10 D1:10 E1:0 G1:13	m2	43		
	Test blocks and testing				
2	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	No	16		
	POLYSTERENE BLOCKS ETC				
	Polystrene blocks in composite slabs				
3	850 x 500mm extreme wide at the bottom, 550mm wide at the top x 110mm high polysterene block laid end to end rows A1: 12 C1: 12 D1: 12 E1: 0 G1: 36	No	72		
	PREFABRICATED CONCRETE RIB				
	25MPa precast reinforced concrete rib				
4	150 x 40mm high concrete rib with two 10mm high tensile reinforcing bars, in lengths not exceeding 5m. A1:6 C1:12 D1:9 E1:0 G1:0	m	27		
5	150 x 40mm high concrete rib with two 10mm high tensile reinforcing bars, in lengths exceeding 5m and not exceeding 7.5m.	m	27		
	A1:0 C1:0 D1:0 E1:0 G1:27				
	<u>FORMWORK</u>				
	Supporting bearers to prefabricated beams				
6	Bearers propped up exceeding 1,5m high and not exceeding 3.5m high A1:18 C1:18 D1:18 E1:0 G1:35	m	88		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS				

	Permanent form	<u>nwork</u>						
1	Soffits of slabs in exceeding 1.5m level.	not exceedir and not exc	ng 250mm tl ceeding 3.5	hick and above bearin	g m2	39		
	A1:8 G1:18	C1:8	D1:5	E1:0	m2	39		
	SECTION NO.3 Bill No. 3 CONCRETE, FO GECELO JPS A	ORMWORK	_E JUNIOR & REINFOI				R	

	Rough formwork	(use and w	aste) to co	ncrete to:				
	Edges, risers, er	nds and reve	<u>eals</u>					
1	Edge, riser, etc r A1 : 17 G1 : 34	not exceedir C1 : 13	ng 300mm D1 : 22	high. E1 : 0	m	86		
	<u>Openings</u>							
2	Leave or form ci through 60mm th A1:5				No	26		
	G1 : 11							
3	Leave or form so through 60mm th				No	9		
	A1 : 2 G1 : 4	C1 : 2	D1 : 1	E1:0				
4	Cut or form circuthrough 110mm		yrene block		No	25		
	A1 : 5 G1 : 11	C1 : 6	D1:3	E1:0				
5	Cut or form squathrough 110mm				No	9		
	A1 : 2 G1 : 4	C1:2	D1 : 1	E1:0				
6	Cut or form circu	ılar opening	not excee	dina 1m airth				
	through permane	ent formworl	k		No	25		
	A1 : 5 G1 : 11	C1 : 6	D1:3	E1:0				
7	Cut or form squathrough permane			ling 1m girth	No	9		
	A1 : 2	C1 : 2	D1 : 1	E1:0				
	G1 : 4							
			Carrie	ed to Collection			R	
	SECTION NO.3	- SONTSEL	E JUNIOR	SECONDARY SO	5			H
	Bill No. 3 CONCRETE, FO GECELO JPS A			RCEMENT				

	Movement joints				
1	10mm Thick closed cell polyethylene joint forming material with hinged blocking piece, not exceeding 300mm wide, between concrete and concrete or brickwork surfaces.	m	86		
	A1:17 C1:13 D1:22 E1:0				
	G1 : 34				
2	Remove 10 x 15mm hinged blocking piece, insert polycord bond breaker and seal with an approved 2 part polysulphide sealer.	m	86		
	A1:17 C1:13 D1:22 E1:0 G1:34				
3	Slip joint not exceeding 300mm wide formed of two layers of 3 Ply malthoid laid on and including a 3:1 cement mortar bedding.	m	86		
	A1:17 C1:13 D1:22 E1:0				
	G1:34				
	REINFORCEMENT (PROVISIONAL)				
	<u>High tensile rod reinforcement to structural concrete</u> <u>work</u>				
4	16mm Diameter bars. A1: 0.107	t	0.382		
5	10mm Diameter bars. A1: 0.174 C1: 0.173 D1: 0.132 E1: 0.000 G1: 0.356	t	0.835		
	High tensile welded steel mesh reinforcement :				
6	Ref: 193 cast into concrete surfaces. A1: 19	m2	95		
7	Ref: 311 cast into concrete surfaces. A1: 12	m2	61		
	Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS			R	

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 3				
CONCRETE, FORMWORK & REINFORCEMENT				
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	111			
	112			
	113			
	114			
	115			
Carried Forward to Summary of Section No. 3		R		
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC BIII No. 3 CONCRETE, FORMWORK & REINFORCEMENT GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 04			
	MASONRY			
	FOUNDATION BRICKWORK (PROVISIONAL)			
	Walls and linings in stock bricks in 5:1 cement mortar:			
1	Half brick wall. m2 A1:5 C1:9 D1:5 E1:0 G1:18	37		
2	One brick wall. m2 A1:30 C1:24 D1:16 E1:0 G1:61	131		
	Reinforcement to brickwork			
3	Galvanised brick reinforcement 75mm wide built horizontally into brickwork. A1:19 C1:39 D1:19 E1:0	155		
	G1:78			
4	Galvanised brick reinforcement 150mm wide built horizontally into brickwork. A1:117 C1:94 D1:117 E1:0	566		
	G1:238			
	EXTERNAL FACE BRICKWORK			
	Allow the Prime Cost of R5 500.00 (Five Thousand Five Hundred Rand) per thousand excluding Vat for Rust Gold face bricks delivered and customer self off loaded to site, pointed with 10mm square vertical and horizontal joints			
5	Extra over ordinary brickwork for facing and pointing in stretcher bond. m2 A1:4 C1:4 D1:5 E1:0 G1:6	19		
	SUPERSTRUCTURE BRICKWORK			
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 4 MANSORY			
	GECELO JPS AND SONTSELE JSS			

	Walls and linings	s in stock b	oricks in 5:1	cement mortar :				
1	Half brick wall. A1:8 G1:21	C1:5	D1 : 14	E1:0	m2	48		
2	One brick wall. A1 : 51 G1 : 70	C1:33	D1 : 49	E1:0	m2	203		
	Beamfilling							
3	Half brick wall. A1:6 G1:9	C1 : 5	D1 : 6	E1:0	m2	26		
	BRICKWORK S	<u>UNDRIES</u>						
	Brickwork air ver	ntilation, et	CC.					
4	Extra over bricky ventilation openii A1 : 60 G1 : 231			120 x 85mm E1:0	No	510		
	Reinforcement to	brickwork	<u><</u>					
5	Galvanised brick horizontally into	brickwork.			m	169		
	A1 : 32 G1 : 76	C1 : 19	D1 : 42	E1:0				
6	Galvanised brick horizontally into		ment 150mm	n wide built	m	550		
	A1 : 146 G1 : 249	C1 : 65	D1:90	E1:0				
	Bagging							
7	Bag down outer	face of inn	er skin of h	rick wall in 4·1				
,	cement slurry.				m2	203		
	A1 : 51 G1 : 70	C1 : 33	D1 : 49	E1:0				
	0							
	Carried to Collection						R	
	SECTION NO.3 Bill No. 4 MANSORY GECELO JPS A			SECONDARY SC				

	Precast pre-stressed reinforced concrete lintols				
1	75 x 110mm Lintol not exceeding 3m long, built at both ends into brickwork over opening. A1:4 C1:5 D1:2 E1:0 G1:5	m	16		
2	90 x 140mm Lintol not exceeding 3m long, built at both ends into brickwork over opening. A1:0 C1:3 D1:0 E1:0 G1:0	m	3		
	Hoop iron ties, cramps, etc.				
3	1.6 x 30mm Galvanized hoop iron roof tie 1100mm long with one end wrapped around and spiked to timber the other end built a minimum of six courses deep into brickwork as the work proceeds.	No	47		
	A1:8 C1:11 D1:12 E1:0 G1:16				
4	30 x 1,2mm Galvanised hoop iron strap 800mm long shot pinned to brickwork and bent into brickwork A1:2 C1:2 D1:2 E1:0	No	8		
	G1:2				
	Allow the Prime Cost of R5 500.00 (Five Thousand Five Hundred Rand) per thousand excluding Vat for Rust Gold face bricks delivered and customer self off loaded to site, pointed with 10mm square vertical and horizontal joints				
5	Extra over ordinary brickwork for facing and pointing in stretcher bond. A1:55 C1:37 D1:55 E1:0 G1:79	m2	226		
	Face brick copings, lintols, cills, etc.				
6	Extra over brickwork for brick-on-edge header course tread including pointing to one face and top. A1:2 C1:3 D1:2 E1:0 G1:2	m	9		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 4 MANSORY GECELO JPS AND SONTSELE JSS				

	Brickwork air ve	entilation, et	tc.					
1	Extra over brick ventilation open	work for fai	ir cutting to foebrick, includ	orm 120 x 85mm ing facing and	No	510		
	pointing A1:60 G1:231	C1: 45	D1:174	E1:0	No	510		
	SECTION NO.3 Bill No. 4 MANSORY GECELO JPS A		ELE JUNIOR	ed to Collection SECONDARY SC			R	

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 4				
MANSORY				
COLLECTION				
Total Brought Forward from Page No.	Page No 117 118 119 120		Amount	
Carried Forward to Summary of Section No. 3		R		_
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 4 MANSORY GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 05			
	WATERPROOFING			
	DAMP-PROOF COURSE			
	SHEET OR MEMBRANE WATERPROOFING			
	250 Micron "Gunplas USB" green polyethylene sheeting :			
1	Laid flat on prepared sand bed under solid floor. m2 A1:18 C1:20 D1:26 E1:0 G1:39	103		
	FLASHING STRIPS			
	Elastic acrylic and rubberised bitumen compound with "waterproof membrane" applied in strict accordance with the Manufacturer's instructions :			
2	Flashing strips around 110mm diameter PVC vent pipes through steel roof sheeting. A1:0 C1:0 D1:0 E1:0 G1:1	2		
	LIQUID WATERPROOFING			
	Two coats "ABE Brickseal"			
3	Vertically on bagged surface of brickwork. m2 A1:49 C1:32 D1:49 E1:0 G1:70	200		
	Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 5 WATERPROOFING GECELO JPS AND SONTSELE JSS		R	

	MEMBRANE WATERPROOFING				
	"Duraflex" or equally approved cementitious flexible waterproofing slurry including saturation membrane with 75mm side and 100mm end laps applied in accordance with manufactures specifications				
1	Vertical surfaces of plastered brickwork. A1: 25 C1: 24 D1: 16 E1: 0 G1: 45	m2	110		
	PROTECTION				
	"Abe Cote SF 356" or other equal approved epoxy tar coating on				
2	Vertical surfaces of plastered brickwork. A1: 25 C1: 24 D1: 16 E1: 0 G1: 45	m2	110		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 5 WATERPROOFING GECELO JPS AND SONTSELE JSS				

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 5				
WATERPROOFING				
COLLECTION				
Total Brought Forward from Page No.	Page No 122 123		Amount	
Carried Forward to Summary of Section No. 3		R		
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 5 WATERPROOFING GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 06			
	ROOF COVERINGS, ETC.			
	PROFILED SHEETING OF METAL, FIBRE CEMENT, PLASTIC, ETC.			
	Metal roof sheeting			
	0,8mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face:			
1	Roof sheeting laid to a mono-pitch secured to timber purlins at approximately 940mm centres including turning up sheet at ridge and turning down sheet at eaves. m2	90		
	A1:18 C1:14 D1:25 E1:0 G1:33			
	<u>Circular cutting</u>			
2	Circular cutting on roof sheeting for ventilators, vent pipes, etc.	6		
	A1:0 C1:2 D1:1 E1:0 G1:3			
	Accessories, etc. to match roof sheeting			
3	Ridge capping 550mm girth.	21		
	A1:4 C1:3 D1:6 E1:0 G1:8			
4	Broad flute serrated closer including polyclosers.	21		
	A1:4 C1:3 D1:6 E1:0 G1:8			
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 6 ROOF COVERINGS, ETC GECELO JPS AND SONTSELE JSS			

1	Narrow flute ser	rrated close	r including p	olyclosers.	m	21		
	A1 : 4	C1:3	D1:6	E1:0				
	G1 : 8							
2	Ridge finial.				No	8		
_	A1 : 2	C1:2	D1:2	E1:0				
	G1 : 2							
			Comie	d to Collection				
			Carrie	ed to Collection			R	
		- SONTSE	LE JUNIOR	SECONDARY SO				
	Bill No. 6 ROOF COVERI	NGS ETC						
	GECELO JPS		SELE JSS					

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 6				
ROOF COVERINGS, ETC				
COLLECTION				
Total Brought Forward from Page No.	Page No 125 126		Amount	
Carried Forward to Summary of Section No. 3		R		
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 6 ROOF COVERINGS, ETC GECELO JPS AND SONTSELE JSS				
			1	

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 07			
	CARPENTRY AND JOINERY			
	CARPENTRY			
	PLATE NAILED TIMBER ROOF CONSTRUCTION			
	Fixing:			
	All nailing of timber roof rafters, purlins, etc shall be done with galvanised nails. In coastal areas, copper, aluminium or stainless steel nails shall be used.			
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to blockwork or concrete.			
	Erection certificates			
1	Contractor is to supply a roof rafters erection certificate for the building stating that the erection and installation of the roof rafters has been inspected and approved by a professional registered structural engineer.	4		
	A1:1 C1:1 D1:1 E1:0			
	G1 : 1			
	Purlins, bracing, etc.			
	Sawn softwood :			
2	38 x 114mm Wall plate wired down (wire ties elsewhere).	63		
	A1:9 C1:13 D1:18 E1:0			
	G1:23	140		
3	50 x 76mm Purlins. m A1:22 C1:17 D1:31 E1:0	110		
	G1:40			
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 7			
	CARPENTRY AND JOINERY			
	GECELO JPS AND SONTSELE JSS			
		1	I	ll I

1	76 x 38mm S5 Treated Timber A1:6 C1:5 D1:6 E1:0 G1:11	m	28		
2	38 x 38 x 152mm Long cleat spiked to rafter foot. A1:8 C1:4 D1:6 E1:0 G1:16	No	34		
3	50 x 76 x 500mm Long sprocket spiked to timber purlin. A1 : 10 C1 : 10 D1 : 10 E1 : 0 G1 : 10	No	40		
	Laminated S. A. Pine				
4	152 x 38mm S5 Timber Rafters A1: 15 C1: 15 D1: 24 E1: 0 G1: 31	m	86		
5	Sundries: Hurricane clip fixed to purlin and rafter. A1: 20 C1: 20 D1: 30 E1: 0 G1: 40	No	110		
	JOINERY Plastic, fibre cement, etc. Pressed fibre-cement:				
6	12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc. A1:4 C1:3 D1:6 E1:0 G1:8	m	21		
7	80 x 275mm Barge board drilled and brass screwed to timber rafter including galvanised steel H-profile jointing strips, etc. A1:8 C1:8 D1:8 E1:0 G1:8	m	32		
	Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 7			R	
	CARPENTRY AND JOINERY GECELO JPS AND SONTSELE JSS				

	TIMBER DOORS, WINDOWS ETC.			ı
	Wrot hardwood :			ı
1	44mm Thick framed, ledged, braced and battened door, size 762 x 1000mm high, comprising 44 x 180mm stiles and top rail, 22 x 180mm bottom rail and diagonal brace and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths. A1:0 C1:3 D1:0 E1:0	о 3		
	Frames and linings			İ
	Wrot hardwood :			İ
2	38 x 100mm Meranti jamb lining bolted to brickwork with and including 10 x 140mm masonry anchors at approximately 600mm centres. A1:0 C1:4 D1:0 E1:0	n 4		
	G1:0			ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
				ı
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC			
	Bill No. 7 CARPENTRY AND JOINERY			ı
	GECELO JPS AND SONTSELE JSS			ı
				ı
				ı

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 7				
CARPENTRY AND JOINERY				
COLLECTION				
Total Brought Forward from Page No.	Page No 128 129 130		Amount	
Carried Forward to Summary of Section No. 3 SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 7 CARPENTRY AND JOINERY GECELO JPS AND SONTSELE JSS		R		

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 08			
	IRONMONGERY			
	IRONMONGERY TO TIMBER			
	<u>Hinges</u>			
1	100 x 75mm Heavy duty brass butt hinges. No A1:0 C1:6 D1:0 E1:0 G1:0	6		
	<u>Handles</u>			
2	100mm Chromium plated pull handle. No A1:0 C1:3 D1:0 E1:0 G1:0	3		
	IRONMONGERY TO METALWORK			
	Locksets, etc. provided with two keys and to be masterkeyed			
3	51mm brass padlock with stainless steel shackle. A1:2 C1:1 D1:2 E1:0 G1:1	6		
	IRONMONGERY FIXED TO CONCRETE, TILING, ETC.			
	Push plates, kicking plates, indicator plates, etc.			
4	152 x 152 x 3mm Thick anodised silver aluminium sex indicator plate. A1:2 C1:1 D1:2 E1:0 G1:1	6		
5	152 x 152 x 3mm Thick anodised silver aluminium			
J	disabled indicator plate. No	1		
	A1:0 C1:0 D1:0 E1:0 G1:1			
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 8 IRONMONGERY GECELO JPS AND SONTSELE JSS			

	3mm Thick x 32mm high clear perspex signs was painted numerals or letters, countersunk tap so steel door frame	vith white crewed to			
1	Sign with "MALE STAFF" enscribed. A1:1 C1:0 D1:0 E1:0 G1:0	No	1		
2	Sign with "FEMALE STAFF" enscribed. A1:1 C1:0 D1:0 E1:0 G1:0 Door stops	No	1		
3	Black rubber door stop plugged to wall. A1:3 C1:3 D1:2 E1:0 G1:6 Sundries	No	14		
4	50mm Plastic key tag. A1:2 C1:1 D1:2 E1:0 G1:2	No	7		
	Carried to Co SECTION NO.3 - SONTSELE JUNIOR SECON Bill No. 8 IRONMONGERY GECELO JPS AND SONTSELE JSS			R	

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 8				
IRONMONGERY				
COLLECTION				
Total Brought Forward from Page No.	Page No 132 133		Amount	
Carried Forward to Summary of Section No. 3 SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC		R		
Bill No. 8 IRONMONGERY GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 09			
	STRUCTURAL STEEL			
	Pre-galvanised (Z450) structural steelwork (Grade 350W)			
1	100 x 50 x 20 x 2mm Cold formed lipped channel including bolting to brickwork at 910mm centres. A1:2 C1:0 D1:2 E1:0 G1:5	9		
	Carried Forward to Summary of Section No. 3		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 9 STRUCTURAL STEEL GECELO JPS AND SONTSELE JSS			

Item No		Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL			
	BILL No. 10			
	<u>METALWORK</u>			
	Hot dipped galvanised mild steel gates			
1	Single gate, size 900mm wide x 2050mm high, the leaf formed of 25 x 25 x 2mm wall thickness mild steel pipe framing all round and two horizontal intermediate rails with mitred and welded angles, the gate filled in with 12mm diameter mild steel bars welded, at each end, vertically to perimeter and intermediate framing at not exceeding 109mm centres, the leaf fitted with a 150mm long padbolt, the leaf to receive hasp and staple formed of 40 x 6mm mild steel flat bar welded onto frames and including fitting with two 50 x 10mm flat bar tee brackets and 16mm round bar pin hinges, twice bolted to wall with and including M16 x 95mm galvanised coach screws. No A1:2 C1:1 D1:2 E1:0	6		
	Hot dipped galvanised mild steel mesh screen			
2	Mesh screen, size 2230mm wide x 2100mm high, formed of 32 x 32 x 2mm wall thickness square hollow section framing all round and two horizontal rails with mitred and welded angles, the framing covered with 50 x 50 x 4mm weld mesh tack welded on, and including fitting with two 50 x 10mm flat bar tee brackets and 16mm round bar pin hinges, twice bolted to wall with and including M16 x 95mm galvanised coach screws.	1		
	A1:0 C1:1 D1:0 E1:0			
	G1:0			
	Carried to Collection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 10 METALWORK GECELO JPS AND SONTSELE JSS			

Door, size 760 x 1680mm high, formed of 19 x 19mm				
tubular steel perimeter framing and horizontal middle rail welded at angles and intersections, covered on one side with 0,6mm galvanised sheeting, prepainted "Golden Brown", pressed to shape with edges lapped around and rivetted to frame at 300mm centres, with slot for and including barrel bolt, the gate fitted with and including 25mm diameter x 2120mm long pivot pipe support welded on, 150 x 38 x 3mm top bearing bolted to beam with 2 x 6mm diameter bolts, including top cap bearing bush, washers, bottom bearing bush and finishing smooth on all exposed edges, complete with all fixing brackets, bolts etc. A1:3 C1:0 D1:2 E1:0 G1:6 Pre-galvanised steel chawl doors	No	11		
Single door to suit one brick wall, size 950 x 2030mm high, provided complete with integral frame, ironmongery, etc. finished with red oxide primer to receive paint (elsewhere). A1:0 C1:0 D1:0 E1:0 G1:1	No	1		
Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 10 METALWORK GECELO JPS AND SONTSELE JSS			R	
	and rivetted to frame at 300mm centres, with slot for and including barrel bolt, the gate fitted with and including 25mm diameter x 2120mm long pivot pipe support welded on, 150 x 38 x 3mm top bearing botted to beam with 2 x 6mm diameter bolts, including top cap bearing bush, washers, bottom bearing bush and finishing smooth on all exposed edges, complete with all fixing brackets, bolts etc. A1:3 C1:0 D1:2 E1:0 G1:6 Pre-galvanised steel chawl doors Single door to suit one brick wall, size 950 x 2030mm high, provided complete with integral frame, ironmongery, etc. finished with red oxide primer to receive paint (elsewhere). A1:0 C1:0 D1:0 E1:0 G1:1 Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 10 METALWORK	and rivetted to frame at 300mm centres, with slot for and including barrel bolt, the gate fitted with and including 25mm diameter x 2120mm long pivot pipe support welded on, 150 x 38 x 3mm top bearing bolted to beam with 2 x 6mm diameter bolts, including top cap bearing bush, washers, bottom bearing bush and finishing smooth on all exposed edges, complete with all fixing brackets, bolts etc. A1:3 C1:0 D1:2 E1:0 G1:6 Pre-galvanised steel chawl doors Single door to suit one brick wall, size 950 x 2030mm high, provided complete with integral frame, ironmongery, etc. finished with red oxide primer to receive paint (elsewhere). A1:0 C1:0 D1:0 E1:0 G1:1 Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 10 METALWORK	and rivetted to frame at 300mm centres, with slot for and including barrel bolt, the gate fitted with and including 25mm diameter x 2120mm long pivot pipe support welded on, 150 x 38 x 3mm top bearing bolted to beam with 2 x 6mm diameter bolts, including top cap bearing bush, washers, bottom bearing bush and finishing smooth on all exposed edges, complete with all fixing brackets, bolts etc. A1:3 C1:0 D1:2 E1:0 G1:6 Pre-galvanised steel chawl doors Single door to suit one brick wall, size 950 x 2030mm high, provided complete with integral frame, ironmongery, etc. finished with red oxide primer to receive paint (elsewhere). A1:0 C1:0 D1:0 E1:0 G1:1 Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 10 METALWORK	and rivelted to frame at 300mm centres, with slot for and including barrel bolt, the gate fitted with and including barrel bolt, the gate fitted with and including 25mm diameter x 2120mm long pivot pipe support welded on, 150 x 38 x 3mm top bearing bolted to beam with 2 x 6mm diameter bolts, including top cap bearing bush, washers, bottom bearing bush and finishing smooth on all exposed edges, complete with all fixing brackets, bolts etc. At:3 C1:0 D1:2 E1:0 G1:6 Pre-galvanised steel chawl doors Single door to suit one brick wall, size 950 x 2030mm high, provided complete with integral frame, ironmongery, etc. finished with red oxide primer to receive paint (elsewhere). A1:0 C1:0 D1:0 E1:0 G1:1 Carried to Collection R SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC BIII No. 10 METALWORK

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 10				
METALWORK				
COLLECTION				
Total Brought Forward from Page No.	Page No 136 137		Amount	
Carried Forward to Summary of Section No. 3		R		
		K		_
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 10 METALWORK GECELO JPS AND SONTSELE JSS				

Item No			Quantity	Rate	Amount
1	SECTION No. 3 - SONTSELE PRIMARY SCHOOL				
	BILL No. 11				
	PLASTERING				
	SCREEDS				
	Untinted granolithic screeds, etc. mixed by volume 4 parts granite chips, 1 part sand and 2 parts cement				
1	40mm Thick screed to floors and landings. A1:11 C1:6 D1:17 E1:0 G1:17	m2	51		
2	25mm Thick screed to falls A1:3 C1:3 D1:2 E1:0 G1:7	m2	15		
	<u>Skirtings</u>				
3	75mm High coved skirting. A1: 18	m	107		
	PLASTER				
	One coat internal 1:4 cement plaster on :				
4	Brick walls in pit. A1:39 C1:32 D1:25 E1:0 G1:113	m2	209		
5	Brick walls (ICP) A1: 76	m2	283		
	Carried Forward to Summary of Section No. 3 SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 11 PLASTERING GECELO JPS AND SONTSELE JSS			R	

ltem No			Quantity	Rate	Amount
140	SECTION No. 3 - SONTSELE PRIMARY SCHOOL				
	BILL No. 12				
	PLUMBING AND DRAINAGE (PROVISIONAL)				
	Roof gutters, rainwater pipes, etc.				
	uPVC gutter including gutter brackets				
1	125mm Half round eaves gutters on gutter brackets at 1000mm centres maximum fixed to fascias.	m	21		
	A1:4 C1:3 D1:6 E1:0				
2	G1:8 Extra over uPVC gutter for forming discharge outlet to suit 100 x 75mm downpipe.	No	4		
	A1:1 C1:1 D1:1 E1:0 G1:1				
3	Extra over gutter for stopped end. A1:2 C1:2 D1:2 E1:0 G1:2	No	8		
4	75mm Rainwater downpipe fixed to wall with and including proprietary holderbats. A1:2 C1:4 D1:4 E1:0 G1:4	m	14		
5	Extra over rainwater downpipe for bend.	No	8		
	A1:2 C1:2 D1:2 E1:0 G1:2				
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 12 PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

	PIPEWORK, ETC.				
	Pipes, pipe fittings, etc.				
	WATER SUPPLIES				
	Class 6 HDPE waterpipe				
1	22mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc. A1:0 C1:0 D1:0 E1:0 G1:12	m	12		
	Extra over Class 6 HDPE pipe for fittings				
2	22mm Fittings. A1:0 C1:0 D1:0 E1:0 G1:10	No	10		
	Class 2 copper pipes with straight compression fittings				
3	15mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc. A1:2 C1:0 D1:10 E1:0	m	12		
	G1:0				
	Extra over copper pipes for brass compression fittings				
4	15mm Fittings.	No	14		
	A1:4 C1:0 D1:10 E1:0 G1:0				
	Extra over copper pipes for capillary fittings with soldered joints				
_					
5	15mm Fittings. A1:2 C1:0 D1:4 E1:0 G1:0	No	6		
	Carried to Collection			R	_
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 12 PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

	SOIL DRAINAG	<u>E</u>						
	uPVC Pipes with	n solvent we	elded straigl	ht joints :				
1	40mm Pipes. A1 : 1 G1 : 0	C1:0	D1:4	E1 : 0	m	5		
2	50mm Pipes. A1:1 G1:0	C1:0	D1:4	E1:0	m	5		
	White uPVC ver	nt pipe in sir	ngle lengths	<u>::</u>				
3	110mm Diamete brackets at not e			II with proprietary res.	m	60		
	A1 : 12 G1 : 28	C1 : 12	D1 : 8	E1 : 0				
	Extra over uPVC	pipes for s	solvent welc	led fittings :				
4	40mm Plain ben A1 : 2 G1 : 0	d. C1:0	D1:8	E1:0	No	10		
5	50mm Plain ben A1:2	d. C1 : 0	D1 : 2	E1:0	No	4		
	G1:0							
6	pipe.	-		r the 110mm vent	No	15		
	A1 : 3 G1 : 7	C1 : 3	D1 : 2	E1 : 0				
	Inspection char		-	=				
	Light Composite	covers and	<u>l frames</u>					
7	screws lock fast holes designed t	and frame ir en cover wi for the easy	nclusive of to th frame and relifting and	wo stainless steel d two vented	No	9		
	G1 : 4	61.2	D1.1	LI.U				
			Carrie	ed to Collection			R	
	SECTION NO.3 Bill No. 12 PLUMBING AND GECELO JPS A	D DRAINAG	SE (PROVIS	SECONDARY SC				

	SANITARY FITT	INGS, TAN	IKS, GEYS	ERS, ETC.				
	Plastic sanitaryw	<u>rare</u>						
1	"Atlas Plastics 23 with integral flap including 6 x 75r A1 : 3 G1 : 7	four times	plugged to		No	15		
2	"Atlas Plastics 50 "496AP" waterle and including pro	ss urinal wa	ste fitting h		No	5		
3	"Atlas Plastics C 245mm, provider in soap holder, h proprietary wall b A1:0 G1:1	d complete ung on wall orackets. C1:0	with two ta	pholes and built	No	1		
4	Sanitary fitting so Satin chrome thi 71, plugged to w A1:3	ef proof toile	et roll holde D1 : 2	er, PWD Sample E1 : 0	No	15		
5	Heavy-duty doub	ole-flap hing C1 : 3	ed toilet se D1 : 2	eat and cover. E1:0	No	15		
	Grade 304 stainl	ess steel w	are :					
6	Grab rail 1200m to wall with and i A1:0 G1:1			s "SR 1" plugged el screws. E1:0	No	1		
7	Dog leg grab rail wall with and inc A1:0 G1:1				No	1		
	SECTION NO.3 Bill No. 12 PLUMBING AND GECELO JPS A	DRAINAG	E JUNIOR E (PROVIS	ed to Collection SECONDARY SC SIONAL)			R	
	GECELU JPS A	ND SUN1S	ELE J33					

	Tanks, geysers, etc. Rainwater tanks				
1	2500 Litre polyethylene rotomoulded vertical wastorage tank complete, on 1600 x 1600 tank staincluding lid, fitted with and including 50 x 15m reducer and setting in position on concrete tank (elsewhere measured) and tying down with 4m diameter galvanised wire wrapped twice around of tank and secured to each corner of tank standouble strand of 4mm diameter galvanised wire embedded into concrete. (Note: tanks to be filled water before Practical Completion).	and, m kstand m d centre nd with a e ed with No	4		
	G1 : 1 <u>Galvanised Steel Pipe</u>				
2	22mm galvanised steel pipe A1:1 C1:1 D1:1 E1:0 G1:1	m	4		
	Taps, valves, etc.				
	Solid cast brass taps, valves, etc.				
3	"Cobra KM2-200" or other equal approved 15m chrome plated metered bib tap with non-hold of feature and flow controller.	pen No	1		
	A1:0 C1:0 D1:0 E1:0 G1:1				
4	15mm Ball-o-stop valve.	No	5		
	A1:1 C1:0 D1:4 E1:0 G1:0				
5	22mm Gate valve	No	4		
	A1:1 C1:1 D1:1 E1:0 G1:1				
6	22mm Non Return valve	No	4		
	A1:1 C1:1 D1:1 E1:0 G1:1				
	Carried to Co	llection		R	
	SECTION NO.3 - SONTSELE JUNIOR SECON Bill No. 12 PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS				

	Waste unions, tra	aps, etc.						
	Outlets, traps, et	<u>:C :</u>						
1	50mm Chromiun A1 : 1 G1 : 0	n plated PV C1 : 0	C urinal bo	ttle trap. E1 : 0	No	5		
2	38mm Chromiun with plug, chain a	n plated bra and chain s C1:0	ass slotted b stay. D1 : 0	pasin waste outlo	et No	1		
	G1 : 1	C1.U	Ы.0	E1.U				
3	38mm PVC Mini A1 : 0 G1 : 1	P-trap. C1:0	D1:0	E1:0	No	1		
			Carrie	ed to Collection	ı		R	
	SECTION NO.3 Bill No. 12 PLUMBING AND GECELO JPS A	DRAINAG	SE (PROVIS		SC			

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 12				
PLUMBING AND DRAINAGE (PROVISIONAL)				
COLLECTION				
COLLECTION Total Brought Forward from Page No.	Page No 140 141 142 143 144 145		Amount	
Carried Forward to Summary of Section No. 3 SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 12 PLUMBING AND DRAINAGE (PROVISIONAL) GECELO JPS AND SONTSELE JSS		R		

Item No			Quantity	Rate	Amount
	SECTION No. 3 - SONTSELE PRIMARY SCHOOL	1			
	BILL No. 13				
	PAINTWORK				
	PAINT ON CONCRETE, PLASTER, ETC				
	Prepare and apply one coat plaster primer, one coat universal undercoat and two coats "Wall & All" or other equal approved washable suede sheen acrylic PVA paint on:				
1	Internal smooth plastered walls.	m2	330		
	A1:76 C1:53 D1:74 E1:0 G1:127				
2	Internal smooth plastered wall in narrow widths not exceeding 300mm wide A1:0 C1:0 D1:1 E1:0 G1:1	m2	3		
	Scrub surface with degreaser, rinse thoroughly with tap water, and apply one coat sealer and two coats epoxy paint on:				
3	Concrete floated or screeded floors A1:11 C1:6 D1:17 E1:0 G1:17	m2	51		
4	Granolithic skirting not exceeding 300mm girth. A1: 20 C1: 19 D1: 29 E1: 0 G1: 47	m	115		
	PAINT ON TIMBER Prime or oil				
5	Backs of frames or linings not exceeding 300mm girth. A1:0 C1:7 D1:0 E1:0 G1:0	m	7		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 13 PAINTWORK GECELO JPS AND SONTSELE JSS				
					l l

1	Doors A1:0 C1:5 D1:0 G1:0	E1:0	m2	5		
	PAINT ON METALWORK					
	Prepare and apply one coat bituminous p	paint on :				
2	Backs of steel door frames. A1:0 C1:0 D1:0 G1:2	E1:0	m2	2		
	One coat steel etch primer, one coat university undercoat and two coats gloss enamel particles.					
3	Hot dipped galvanised steel gates. A1:4 C1:2 D1:4 G1:2	E1:0	m2	12		
4	Hot dipped galvanised steel mesh screen A1:0 C1:5 D1:0 G1:0	ns. E1:0	m2	5		
	One coat red oxide primer, one coat univand two coats gloss enamel paint on :	ersal undercoat				
5	Pre-galvanised steel doors. A1:0 C1:0 D1:0 G1:2	E1:0	m2	2		
6	Pre-galvanised steel door frames. A1:0 C1:0 D1:0 G1:2	E1:0	m2	2		
	PAINT ON FIBRE-CEMENT					
	Prepare and apply one coat plaster prime coats quality matt acrylic PVA on :	er and two				
7	External fibre cement fascia boarding inc cover strips. A1:1 C1:1 D1:1 G1:2	luding priming E1:0	m2	5		
	Carried	to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR S Bill No. 13 PAINTWORK GECELO JPS AND SONTSELE JSS	ECONDARY SC				

1	External fibre ce cover strips.	ment barge	board inclu	ding priming	m2	8		
	A1 : 2	C1:2	D1:2	E1:0				
	G1 : 2							
	PAINT ON PVC							
	Prepare and app	oly two coat	s black PV	A paint on:				
2	Vent pipes. A1:1 G1:3	C1:1	D1:1	E1:0	m2	6		
	SECTION NO.3 Bill No. 13 PAINTWORK GECELO JPS A		_E JUNIOR	ed to Collection SECONDARY S	C		R	

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 13				
PAINTWORK				
COLLECTION				
Total Brought Forward from Page No.	Page No 147 148 149		Amount	
Carried Forward to Summary of Section No. 3		R		<u>_</u>
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 13 PAINTWORK GECELO JPS AND SONTSELE JSS				

Item No		Quantity	Rate	Amount
	SECTION No. 3 - EXTERNAL WORKS - SONTSELE PRIMARY SCHOOL			
	BILL No. 14			
	EXTERNAL WORKS (PROVISIONAL)			
	Note:			
	For Preambles see "PW 371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013).			
	<u>DEMOLITIONS</u>			
	<u>Demolitions</u>			
	Brickwork building structures			
1	Demolish and cart away single storey toilet block complete, size on plan 4000mm long x 2500mm wide x approximately 2800mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, brick and mortar walls with metal doors, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	1		
2	Demolish and cart away single storey toilet block complete, size on plan 4500mm long x 3000mm wide x approximately 2800mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, brick and mortar walls with metal doors, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	1		
	Carried to Collection SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS		R	

1	Demolish and cart away single storey toilet block complete, size on plan 8000mm long x 3000mm wide x approximately 2800mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, brick and mortar walls with metal doors, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	No	1		
2	Demolish and cart away single storey toilet block complete, size on plan 8400mm long x 3200mm wide x approximately 2800mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, brick and mortar walls with metal doors, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	No	1		
	<u>Pit toilets</u>				
3	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out.	No	4		
4	Allow for breaking down and removing from site entire pit latrine structure including any structure that may be inside the pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured). Backfill existing hole with imported filling in max 150mm layers and compact to 95% MOD AASHTO density.	No	4		
	THE FOLLOWING IN WALKWAYS, RAMPS, ETC.				
	<u>EARTHWORKS</u>				
	Site clearance				
5	Clear the areas to be developed of all rubbish, debris, vegetation, shrubs, bush and small trees not exceeding 200mm girth and remove from site.	m2	120		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	Excavate in earth not exceeding 2m deep including				
	trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
1	Reduced levels under solid floors.	m3	24		
	Carting away of excavated material				
2	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	24		
	Filling				
3	150mm G7 Sub-base course, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 93% modified AASHTO density under slabs.	m3	18		
	Prescribed Testing				
4	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.	No	2		
	Reinforced concrete 25MPa (19mm stone) in:				
5	Paving in panels including any necessary formwork.	m3	12		
6	Ramps.	m3	0.4		
	Surface treatment				
7	Float surface of concrete to a wood float finish.	m2	120		
	Test blocks and testing				
8	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	No	2		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	Movement joints				
1	10mm Thick "Jointex" closed cell polyethylene joint filler with hinged blocking piece between concrete surfaces not exceeding 300mm wide.	m	33		
2	Remove hinged blocking piece and fill 10 x 15mm cavity with an approved 2 part polysulphide sealer.	m	33		
	<u>FORMWORK</u>				
	Edges, risers, ends and reveals				
3	Edge, riser, etc not exceeding 300mm high.	m	200		
	Reinforcement				
4	Ref: 193 High tensile welded steel mesh reinforcement cast into concrete surfaces.	m2	120		
	THE FOLLOWING IN STORMWATER CUT OFF DRAIN / EARTH BERM				
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
5	Reduced levels	m3	30		
	Filling				
6	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	30		
	Compaction of surfaces				
7	Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density.	m2	60		
	Grassing, ground cover, etc.				
8	Kikuyu turf (sods or rolls) instant lawn 25 to 40mm thick, imported from commercial sources, laid firmly with staggered joints within three days of being lifted.	m2	50		
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	THE FOLLOWING IN CONCRETE CHANNELS, ETC.				
	<u>EARTHWORKS</u>				
1	Holes	m3	0.3		
2	Surface trenches.	m3	1		
	Carting away of excavated material				
3	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	1		
4	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	1		
	Sundries				
5	Rip prepared platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	3		
	Prescribed Testing				
6	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.	No	4		
	<u>FORMWORK</u>				
	Edges, risers, ends and reveals				
7	Edge, riser, etc not exceeding 300mm high.	m	6		
	Grooves, channels, mortices, etc.				
8	700 x 150mm V-Channels in top	m	3		
9	1500 x 750 x 150mm Concrete V-Channel Spreader	No	1		
	REINFORCEMENT (PROVISIONAL)				
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

ı		1	1	I	1	1
	High tensile rod reinforcement to structural concrete work					
1	12mm Diameter bars.	t	0.007			
	Reinforcement					
2	Ref: 193 High tensile welded steel mesh reinforcement cast into concrete surfaces.	m2	3			
	THE FOLLOWING IN STAND PIPE BIP TAP ETC.					
	<u>EARTHWORKS</u>					
3	Holes	m3	1			
4	Surface trenches.	m3	6			
	Carting away of excavated material					
5	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	1			
	Risk of collapse of excavations					
6	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	7			
	Keeping excavations free of water					
7	Allow for keeping the excavations free from water.		Item			
	Filling					
8	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	6			
	Foundation courses					
9	Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc.	m3	0.3			
	Carried to Collection			R		
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS					

	Sundries				
1	Rip prepared platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	2		
	Prescribed Testing				
2	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.	No	2		
	CONCRETE (Labour intensive)				
	Mass concrete 25MPa (19mm stone) in:				
3	Strip foundations cast against excavated surfaces.	m3	2		
	Reinforced concrete 25MPa (19mm stone) in:				
4	Slabs	m3	1		
5	110mm PVC Blue Water Pipe	m3	1		
	<u>FORMWORK</u>				
	Edges, risers, ends and reveals				
6	Edge, riser, etc not exceeding 300mm high.	m	3		
	REINFORCEMENT (PROVISIONAL)				
	High tensile rod reinforcement to structural concrete work				
7	12mm Diameter bars.	t	0.003		
	PIPEWORK, ETC.				
	Pipes, pipe fittings, etc.				
	WATER SUPPLIES				
					_
	Carried to Collection			R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS				

	Class 2 copper pipes with straight compression fittings					
1	22mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc.	m	46			
	Extra over copper pipes for brass compression fittings					
2	22mm Fittings.	No	12			
	uPVC Pipes					
3	110mm Blue Water Pipe.	m	7			
	SANITARY FITTINGS					
	Solid cast brass taps, valves, etc.					
4	Bib Tap or Similar approved	No	4			
	Carried to Collection			R		_
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SO	;				_
	Bill No. 14 EXTERNAL WORKS					
	GECELO JPS AND SONTSELE JSS					
- 1		I		ı	(I	

Section No. 3				
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL				
Bill No. 14				
EXTERNAL WORKS				
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	151			ļ
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL Bill No. 14 EXTERNAL WORKS	152			
	153			
	154			ļ
	155			
	156			
	157			ļ
	158			
		_		_
		R		
Bill No. 14 EXTERNAL WORKS				
SECTED OF AND CONTOLLE COO				

	Section No. 3			
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL			
	SECTION SUMMARY - SECTION NO.3 - SONTSELE JUNIOR SEC	ONDARY S		
Bill No		Page No		Amount
1	PREMILINARIES AND GENERAL	104		
2	EARTHWORKS (PROVISIONAL)	110		
3	CONCRETE, FORMWORK & REINFORCEMENT	116		
4	MANSORY	121		
5	WATERPROOFING	124		
6	ROOF COVERINGS, ETC	127		
7	CARPENTRY AND JOINERY	131		
8	IRONMONGERY	134		
9	STRUCTURAL STEEL	135		
10	METALWORK	138		
11	PLASTERING	139		
12	PLUMBING AND DRAINAGE (PROVISIONAL)	146		
13	PAINTWORK	150		
14	EXTERNAL WORKS	159		
	Sub-Total		R	
	Carried Forward		R	
	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC Bill No. 14 EXTERNAL WORKS GECELO JPS AND SONTSELE JSS			

Section No. 3			
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL			
SECTION SUMMARY - SECTION NO.3 - SONTSELE JUNIOR SE	ECONDARY S		
	Page No		Amount
Brought Forward		R	
CONTINGENCY PROVISIONS			
The Tenderer is to allow hereunder for 5 (Five) percent of the Nett Builders Work Sub-Total to be used as a Budgetary Provision for construction contingencies of a general nature and for the finalisation of design detailing. This sum, or any portion thereof, shall be expended at the sole discretion of the Principal Agent. Any residual balance remaining subsequent to such expenditure shall be deducted in its entirety from the			
Contract Sum.	%		
Carried to Final Summary		R	
SECTION NO.3 - SONTSELE JUNIOR SECONDARY SC GECELO JPS AND SONTSELE JSS			

	FINAL SUMMARY				1
Section No		Page No		Amount	
1	PRELIMINARIES AND GENERAL (NOT TO BE PRICED, P&G PRICED PER SCHOOL SECTION)	46			
2	SECTION NO.2 - GECELO JUNIOR PRIMARY SCHOOL	103			
3	SECTION NO.3 - SONTSELE JUNIOR SECONDARY SCHOOL	161			
	Sub-Total		R		
	Add Value - Added Tax at the rate applicable as at Tender closing date.		R		
	Carried to Form of Tender		R		
	GECELO JPS AND SONTSELE JSS				
]